

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20630-00-00
Spot: N2NWSW Sec/Twnshp/Rge: 9-16S-10W
2310 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: BOYE Well Number: 1
County: ELLSWORTH Total Vertical Depth: 3362 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Production Casing Size: 4.5 feet: 3362 175 SX CMT
Surface Casing Size: 8.625 feet: 301 175 SX CMT

#109²⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/05/2003 2:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: VERNON PHFLUEGEOFT Company: D S & W WELL SERVICING, INC. Phone: (620) 793-2440

Proposed Plugging Method: Sand off perforations to 3280' and put 4 sacks of cement on top. Perforate at 1300', 950', and 350'. Run tubing to 1300' and pump 35 sacks of cement. Pull tubing to 950' and pump 35 sacks of cement. Pull tubing to 350' and circulate cement to surface.

Plugging Proposal Received By: JACK LUTHI Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 11/05/2003 3:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sand off perforations to 3284' and put 4 sacks of cement on top. Perforate at 1300', 950', and 350'. Run tubing to 1300' and pump 35 sacks of cement with 100 lbs of cotton hulls. Pull tubing to 950' and pump 35 sacks of cement. Pull tubing to 350' and circulate cement to surface.

60/40 poz mix with 4% gel.

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 17 2003
CONSERVATION DIVISION
WICHITA, KS
RECEIVED
KCC DISTRICT #2
NOV 7 2003
WICHITA, KS

Remarks: ALLIED TICKET #12856

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 11-18-03
INV. NO. 2004060775