

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20249-00-01
Spot: SENE SW Sec/Twnshp/Rge: 12-10S-24W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: S E GANO UNIT Well Number: 2-1 INJ
County: GRAHAM Total Vertical Depth: 4081 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 4079 200 1st, 500 2nd SX CMT
Surface Casing Size: 8.625 feet: 181 150 SX CMT

132⁶³

Well Type: EOR UIC Docket No: E24173.1 Date/Time to Plug: 11/04/2003 9:00 AM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered out 200 sxs Swift Multi-Density Cement with 500# hulls.
DV Tool at 2124' w/500 sxs cement.
Perfs 3798' - 4008'.
Wireline TD 3876'.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/04/2003 11:15 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2516'. Swift Services pumped 75 sxs cement with 300# hulls.
Pulled tubing to 653'. Swift Services pumped 55 sxs cement with 200# hulls - cement circulated.
PTOH. Squeezed with 18 sxs cement.
Max. P.S.I. 400#. S.I.P. 200#.
Hooked up to backside - pumped 12 sxs cement.
Max. P.S.I. 400#. S.I.P. 200#.

RECEIVED

NOV 17 2003

KCC WICHITA

Remarks: LEASE ALSO KNOWN AS BEESLEY #1. SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 11-18-03

INV. NO. 2004060785

NOV 06 2003

DON E. PRATT #1 BEESLEY 12-10-24W
 HAYS, KS. SE NE SW
 Contr. GARVEY DRLG. Cty. GRAHAM
 Geol. J. R. GREEN Pool GANO SE CONF
 E. 2483 KB Cm. 7/28/69 Cp. 9/18/69 IP PMP 135 BOPD +
 20%W/LKC 3984-90
 API 15-065-20,249 GR 44

LOG Tops	Depth'	Datum	
ANH	2092	+ 391	Csg. 8" 191/200 sx; 4 1/2" 4079/200 sx DV TOOL IN ANH W/400 sx
TOP	3557	-1074	DST 3770-3810/2', 120'M, BHP 1305-1233#/30" FP 25-89#
HEEB	3774	-1291	DST 3806-53/1', GTS/30", 3384' CGO, BHP 1342-1323#/30", FP 214-1143#
TOR	3796	-1313	DST 3853-76/1', 1856' GIP, 402' CGO, BHP 743-1017#/30", FP 35-160#
LKC	3814	-1331	DST 3875-3906/1', 20'M & 965' MGCSW W/TR OIL, BHP 896-887#/30", FP 17-482#
BKC	3970	-1487	DST 3932-74/1', GTS/30", 3562' CGCO, BHP 1386-1372#/30", FP 339-1215#
LTD	4081	-1598	DST 3972-4002/1', GTS/17" OIL IN 50", SI- FLO 10", REC OUT 4002' CGO, BHP 1341- 1343#/30", FP 196-1161#
RTD	4081	-1598	DST 3996-40/8/1', 500' MCO, 2380'W (15% OIL.) BHP 1258-1200# (EST CLOOF STOPPED) FP 327-1068# (OVER)

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

DON E. PRATT #1 BEESLEY 12-10-24W
 SE NE SW
 PF 24/3984-90, FU 1000' OIL/15", FU 3400' OIL/2 1/2 HRS, A 1150, SI/12 HRS, SWB
 THRU TBG, 18 BO--KICKED OFF & FLO 29 1/2 BOPH, N/T 3/8" CK, FLO 30 BOPH, N/T

MAOICED