

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20601-00-00  
Spot: SESESE Sec/Twnshp/Rge: 29-9S-24W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: GEORGE NICKELSON Well Number: 8  
County: GRAHAM Total Vertical Depth: 4071 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 4131 200 SX CMT  
Surface Casing Size: 8.625 feet: 247 170 SX CMT

#132<sup>31</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/05/2003 9:00 AM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered out 200 sxs Swift Multi-Density Cement with 500# hulls.  
No squeeze records. Perforate Anhy 2125' and Base Dakota 1075'.  
Prod. Perfs 4015' - 4080'. Was producing under packer at 4021'  
Backed off packer at 4028' with three joints tail pipe.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/05/2003 1:20 PM

KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Perforated at 2125' - 1075'.  
Ran tubing to 2154'. Swift Services pumped 10 sxs neat cement, followed with 100 sxs and 500# hulls - circulated cement.  
PTOH. Swift Services squeezed with 35 sxs cement with 50# hulls.  
Max. P.S.I. 300#. S.I.P. 100#.  
Hooked up to backside. Swift Services pumped 30 sxs cement with 50# hulls.  
Max. P.S.I. 100#. S.I.P. 100#.

RECEIVED  
NOV 17 2003  
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS HOETING UNIT #2-8. SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

*Richard Williams*

(TECHNICIAN)

INVOICED

DATE

11-18-03

INV. NO.

2004060785

NOV 07 2003

