

RECEIVED

NOV 07 2003

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERRY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD KCC WICHITA

API NUMBER 15-129-00544-0000

LEASE NAME Estelle Smith

WELL NUMBER #1

SPOT LOCATION C-SE

SEC. 19 TWP. 31 RGE. 40 (E) OR (W)

COUNTY Morton

DATE WELL COMPLETED

PLUGGING COMMENCED 10-21-03

PLUGGING COMPLETED 10-24-03

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Westport Resources

ADDRESS 5735 Pineland, Suite 300, Dallas Texas 75231

PHONE #(918) 481-6020 OPERATORS LICENSE NO. 31269

CHARACTER OF WELL Oil
(OIL) (GAS) D&A, SWD, INPUT, WATER SUPPLY WELL

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City

IS ACO-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED?

PRODUCING FORMATION Herrington DEPTH TO TOP 2200 BOTTOM 2224 T.D. 2277

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Herrington	Oil Gas Water	2200	2224	8 5/8	479	-0-
Open hole - KRIDER		2248	2258	5 1/2	2248	901
<u>Cchase group</u>						

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Lay down tubing. Flush hole with 120 bbl mud set CIBP @2170' with 2 sx cement on top. Load hole with 60 bbl mud. Cut off 5 1/2 casing @900' circulate hole with 55 bbl mud. mix & pump 50 sx. cement from 900' to 750'. Pull casing up to 500'. mix & pump 50 sx. cement from 500 to 350'. Pull casing up to 40'. Mix & pump 20 sx. cement 40' to surface. Cut off & weld steel I.D. plate 4' B.G.L.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Jerry Dunkin, Inc.

ADDRESS P.O. Box 389 Enid, Oklahoma 73702

LICENSE No. 8733

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Steven Kleinert

(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE)


8908 S. Yale, Ste. 340
Tulsa, OK 74137-3522

(ADDRESS)

SUBSCRIBED AND SWORN TO BEFORE ME THIS 3rd DAY OF November 19 2003

NOTARY PUBLIC

MY COMMISSION EXPIRES: 1-23-2005



#97001265

FORM CP-4
REVISED 06-83