

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-053-20630-00-00

API NUMBER NA

LEASE NAME Boye

WELL NUMBER #1

2310 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 9 TWP. 16s RGE. 10 (E) or (W)

COUNTY Ellsworth

Date Well Completed _____

Plugging Commenced 11/04/03

Plugging Completed 11/05/03

NOV 13 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR American Warrior

ADDRESS P.O. Box 399, Garden City, Ks 67846

PHONE (620) 275-2963 OPERATORS LICENSE NO. 4058

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 3rd, 2003 (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top 3325' Bottom 3356' T.D. 3362'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0'	301'	8-5/8"	301'	0'
	Production	0'	3362'	4-1/2"	3362'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Rigged up & sanded well of to 3284'. Put 4sx cement on bottom. Tied onto 4-1/2"-picked up on it. Pulled 5' sub out collar. Went after 8' sub. Screwed back onto collar-set casing jacks. Pulled stretch into pipe. Pulled collar off joint in hole. Screwed back-pulled off again. Hauled 1300' workstring out. Had Perf-lech perf. 1300'-950'-350'. Run tubing into 1300'-pumped 35sx-100# hulls. Pulled to 950'-pumped 35sx-pulled to 350'-pumped 80sx-well wasn't cir. Pulled tubing out. Top well with 100sx-200# hulls. Well was falling back. Tore jacks and rig down and moved off.

Name of Plugging Contractor D. S. & W. Well Servicing License No. 6901

Address P.O. Box 231, Claflin, Ks 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Warrior

STATE OF Kansas COUNTY OF Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Edward S. Nemnich
(Address) P.O. Box 231, Claflin, Ks 67525

SUBSCRIBED AND SWORN before me this 11th day of November, 2003

KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt Expires 4/13/06

Karen J. Mitchell
Notary Public

My Commission Expires: April 13th, 2006