

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-19011-00-00
Spot: NE Sec/Twnshp/Rge: 34-19S-7E
5052 feet from S Section Line, 526 feet from E Section Line
Lease/Unit Name: STARKEY Well Number: 7-X
County: CHASE Total Vertical Depth: 666 feet

Operator License No.: 5399 Conductor Pipe Size: feet: 40
Op Name: AMERICAN ENERGIES CORPORATION Production Casing Size: 2 feet: 666 PRODUCTION TUBING
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

Well Type: GAS UIC Docket No: Date/Time to Plug: 11/21/2003 5:30 PM
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.
Proposal Rcvd. from: LAWRENCE W. JACKSON Company: AMERICAN ENERGIES CORP Phone: (620) 793-2146

Proposed
Plugging
Method:

IN ACCORDANCE WITH THE KANSAS CORPORATION'S RULES AND REGULATIONS.
RECEIVED
KCC DISTRICT #2
NOV 25 2003
WICHITA, KS

Plugging Proposal Received By: MICHAEL WILSON Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 11/22/2003 9:30 AM KCC Agent: BILL JOHNSON

Actual Plugging Report:

Ran 3/4" tubing in 2" tubing to depth of 666', cemented with 57 sx 60/40 posmix; ran 1" tubing outside 2" to a depth of 210'. Cemented with 149 sx of common with 3% calcium chloride. Finished this part at 5:30 pm 11/21/03.
Drill outside conductor pipe on 11/22/03 to depth of 40'. Cemented with 37 sx 60/40 posmix 2% gel, top off 2" tubing with 13 sx of 60/40 posmix. 9:30 am.
Actual TVD of casing and tubing could not be verified. An 666' was used as TVD for plugging documentation.
Used 60/40 posmix with 2% gel & common cemented with 2% CC outside 2" tubing.

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 25 2003
CONSERVATION DIVISION
WICHITA, KS

Remarks: UNITED CEMENTING TICKET #5040

Plugged through: TBG

District: 02

Signed Bill Johnson
(TECHNICIAN)

INVOICED
DATE 11-26-03
INV. NO. 2004060828