

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-19007-00-00
Spot: NE Sec/Twnshp/Rge: 34-19S-7E
4612 feet from S Section Line, 414 feet from E Section Line
Lease/Unit Name: STARKEY Well Number: 3-X
County: CHASE Total Vertical Depth: 780 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

Production Casing Size: 2.375 feet: 780

35⁰⁰

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/21/2003 10:00 AM
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.
Proposal Rcvd. from: LAWRENCE W. JACKSON Company: AMERICAN ENGERGIES CORP. Phone: (620) 793-2146

Proposed
Plugging
Method:

IN ACCOORDANCE WITH THE KANSAS CORPORATION'S RULES AND REGULATIONS.

RECEIVED
DISTRICT #2

NOV 25 2003

WICHITA, KS

Plugging Proposal Received By: MICHAEL WILSON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/21/2003 12:25 PM KCC Agent: BILL JOHNSON

Actual Plugging Report:

Ran 3/4" tubing in well to a depth of 780' circulated fluid, cemented from 262' w/28 sx; hole in tubing at approx 135'. Ran 1" tubing outside 2-3/8" tubing to depth of 248', cement with 112 sx, cir. Cement inside and outside 2-3/8" tubing. Drill backside of 8" conductor pipe to depth of 55'. Ran 1" tubing and cemented from 52' with 28 sx to surface.

Actual total vertical depth, conductor pipe, casing, and tubing could not verified. The estimated depth of 780' TVD was used for this plugging documentation.

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 25 2003

CONSERVATION DIVISION
WICHITA, KS

Remarks: UNITED CEMENTING TICKET #5039 60/40 POSMIX WITH 2% GEL

Plugged through: TBG

District: 02

INVOICE
Signed: *Bill Johnson*
(TECHNICIAN)
11-24-03
2004060828