

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-21535-00-00
Spot: SESENWNW Sec/Twnshp/Rge: 5-30S-35W
1250 feet from N Section Line, 1250 feet from W Section Line
Lease/Unit Name: BROLLIER JERRY Well Number: 1-5R
County: GRANT Total Vertical Depth: 2760 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA.
Address: 5205 N. O'CONNOR BLVD.
IRVING, TX 75039

Production Casing Size: 5.5 feet: 2760 WITH 510 SX CMT
Surface Casing Size: 8.625 feet: 547 WITH 350 SX CMT

89 70

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/24/2003 10:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 500# HULLS & 25 SX CMT. TAG PLUG AND PUMP CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/24/2003 12:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:


PBTD 2738'. PERFS AT 2580-2618. CIBP @ 2576'. PERFS AT 2375-2572'. PUMPED DOWN 5 1/2" 500# HULLS MIXED IN 20 BBL MUD & 25 SX CMT DISPLACE WITH 25 BBL MUD. FL @ 1100'. SHUT DOWN. TAGGED BOTTOM PLUG AT 2090'. FL @ 1123'. PUMPED 10 BBL MUD SPACER TO 650'. CMT TO SURFACE WITH 83 SX CMT. PRESSURED UP TO 500# & SHUT IN. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 10 SX CMT. PRESSURED UP TO 500# AND SHUT IN.

RECEIVED
DEC 02 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Kevin P Strube

(TECHNICIAN)

INVOICED
DATE 12-2-03
INV. NO. 2004060847

Form CR-23