

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 207
WICHITA, KANSAS 6720

API Well Number: 15-017-19005-00-00
Spot: NE Sec/Twnshp/Rge: 34-19S-7E
4897 feet from S Section Line, 893 feet from E Section Line
Lease/Unit Name: STARKEY Well Number: 2-X
County: CHASE Total Vertical Depth: 243 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

Surface Casing Size: 6.625 feet: 243

35°

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/22/2003 8:00 AM
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.
Proposal Rcvd. from: LAWRENCE W. JACKSON Company: AMERICAN ENERGIES CORP. Phone: (620) 793-2146

Proposed Plugging Method: IN ACCORDANCE WITH THE KANSAS CORPORATION'S RULES AND REGULATIONS.
RECEIVED
KCC DISTRICT #2
NOV 24 2003
WICHITA, KS

Plugging Proposal Received By: MICHAEL WILSON
Date/Time Plugging Completed: 11/22/2003 11:00 AM

Witness Type: Plugging Operations Partially Witnessed
KCC Agent: BILL JOHNSON

Actual Plugging Report:

11/18/03 -- Wash down with 1" tubing to 243'. Cement with 49 sacks of 60/40 pos mix. Cannot get tubing between 6-5/8" and 8-5/8" casing. Orange peel 8-5/8" and weld to 6-5/8". Cut hole on side of 8-5/8" and weld on nipple. Pump cement between pipe with 119 sacks of 60/40 pos mix. Had approx 15 sacks flow back. Installed valve to shut off flow back of cement.
11/22/03 -- Drill down back side into bed rock at approx 40'. Cement with 37 sacks of 60/40 pos mix with 4% gel.
Actual Total Vertical Depth, surface casing, and production casing could not be verified. An estimate of 243' was used for plugging documentation.
Used 60/40 pos mix with 4% gel.

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 25 2003
CONSERVATION DIVISION
WICHITA, KS

Remarks: UNITED CEMENTING TICKET #5037 = 168 SX AND TICKET #5185 = 37 SX

Plugged through: TBG

District: 02

Signed Bill Johnson
(TECHNICIAN)

INVOICED
DATE 11-25-03
INV. NO. 2004060823