

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-22651-00-00
Spot: NWNENW Sec/Twnshp/Rge: 25-23S-3E
4950 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: PAULSON C Well Number: 7
County: BUTLER Total Vertical Depth: 2550 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. D/B/A TE-PE OIL &
Address: PO BOX 522
CANTON, KS 67428

Production Casing Size: 5.5 feet: 2548 140 SX CMT
Surface Casing Size: 8.625 feet: 209 150 SX CMT

82 88

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/18/2003 9:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE JOE Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Sand back 50' above perforations @ 2210' - 2215' @ 2224' - 2225-1/2'. CIBP @ 2400'. Cement from 300' to surface.

Plugging Proposal Received By: JACK LUTHI Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/18/2003 10:50 AM KCC Agent: JEFF KLOCK

Actual Plugging Report:

Shot 5-1/2" casing off @ 1355'. Pull to 280' and pumped 90 sacks of cement. Pulled 5-1/2" casing out of hole and pumped 20 sacks of cement down surface casing to top off. Circulate cement to surface; good returns.

Note: Hole was sanded back to 2140'.

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 25 2003

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
KCC DISTRICT #2

NOV 19 2003

WICHITA, KS

Remarks: BLUE STAR ACID SERVICE, INC. TICKET #5118 60/40 POZMIX WITH 4% GEL

Plugged through: CSG

District: 02

Signed

Jeff Klock

(TECHNICIAN)

INVOICEU

DATE 11-25-03

NOV. NO. 2004060825