

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20931-00-00
Spot: NWNENE Sec/Twnshp/Rge: 16-1S-26W
330 feet from N Section Line, 930 feet from E Section Line
Lease/Unit Name: E HUFF Well Number: 1-16
County: DECATUR Total Vertical Depth: 3526 feet

Operator License No.: 31956
Op Name: FRICKEY, DOUGLAS C. DBA DARK HO
Address: 34861 FOREST PARK DR.
ELIZABETH, CO 80107

Surface Casing Size: 8.625 feet: 212

\$114⁶⁰

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/16/2003 8:00 AM
Plug Co. License No.: 30076 Plug Co. Name: ANDERSON, ANDY DBA A & A PRODUCTION
Proposal Rcvd. from: DARRELL ANDERSON Company: ANDERSON, ANDY DBA A & A PR Phone: (785) 421-6266

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 10/17/2003 5:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st. Plug at 1925' w/25 sxs cement.
2nd. Plug at 1200' w/100 sxs cement.
3rd. Plug at 275' w/40 sxs cement.
4th. Plug at 40' w/10 sxs cement.
Rathole with 15 sxs.

RECEIVED
NOV 21 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed [Signature]
(TECHNICIAN)

INVOICED

DATE 11-21-03

NY. NO. 2004060809

NOV 17 2003