

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-30477-00-00
Spot: NWSESE Sec/Twnshp/Rge: 5-19S-12W
990 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: HULLMAN A Well Number: 2
County: BARTON Total Vertical Depth: 3371 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B 7 SW 26TH AVENUE
GREAT BEND, KS 67530

Production Casing Size: 5.5 feet: 3365 75 SX CMT
Surface Casing Size: 8.625 feet: 182 150 S XCMT **\$109 SK**

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/06/2003 12:00 PM
Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/06/2003 1:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Pumped 75 sxs 60/40 pozmix - 10% gel cement down backside.
Max. P.S.I. 400#. S.I.P. 150#.
Pumped 245 sxs cement with 600# hulls down casing.
Max. P.S.I. 900#. S.I.P. 450#.

RECEIVED
NOV 21 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.
Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)

INVOICED
DATE 11-21-03
INV. NO. 2004060811

NOV 17 2003

MADICED

11-75 Map No.
 OPER RAYMOND OIL CO.
 WICHITA, KS.
 WELL #2 HULLMAN 'A'
 CONTR CO TOOLS
 FIELD CONF - CHEYENNE WEST FIELD (ARB)
 I.P. STATE POT: P 110 BOPD + TR WTR GR 39 DEG
 ARB 3365 - 87

CTR 5-195-12M
 SPOT NW SE SE
 CO BARTON, KS.
 ELEV 1810 KB

KB LOG:
 ANH 633+1177
 B/" 658+1152
 TOP 2712-902
 HB SH 2978-1168
 BL 3090-1280
 LAN 3103-1293
 CGL 3344-1534
 ARB 3363-1553
 LTD 3371-1561
 RTD 3371-1561
 DCTD 3387-1577

SPUD 10-12-66 8" 182 W/150 SX GEOL - GEORGE OLDS
 DST #1 (LAN) 3104-58, OP 39", R 12' M + VSSO, ISIP 659#/30"
 FP'S 39-78#, FSIP 133#/30" (BHT 105)
 DST #2 (LAN) 3138-74, OP NA, 490' GIP, R 69' SOCM, ISIP
 275#/NT, FP'S 39-47#, FSIP 141#/NT
 DST #3 (LAN) 3225-86, OP 70", R 5' OCM + 540' SW, ISIP 1065#/
 30", FP'S 109-219#, FSIP 941#/30" (BHT 109)
 DST #4 (LAN) 3288-3320, OP 70" 2160' GIP, R 30' OCM + 420'
 SMC&GCO + 180' FROG OIL, ISIP 442#/30", FP'S 149-244#,
 FSIP 434#/30" (BHT 108)
 RTD 3371, LOG, 5 1/2" 3365 W/75 SX
 MICT, CO & DD 3387' 1000 A, 5 LD, 5 BCPH/4 HRS,
 POP, STATE POT: P 110 BOPD + TR WTR (GR 39 DEG)
 ARB 3365-87 TD COMPLETED 11-9-66

KB SPL:
 ANH 637
 B/ANH 662
 TOP 2715
 HB 2980
 BL 3090
 LAN 3102
 RTD 3371

MISCEL DATA	GEOL	GEORGE OLDS	ELEV	1808 DF	SPUD DATE	10-12-66
	FTG			1805 GR	DRLG COMP	
	SUPPT				FR by DATA	10-6-66
	CSG	8" 182/150 SX	5 1/2" 3365/75 SX		COMP by "	11-10-66