

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-22134-00-00  
Spot: E2SESW Sec/Twnshp/Rge: 5-19S-12W  
660 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: DAVIS Well Number: 1  
County: BARTON Total Vertical Depth: 3390 feet

Operator License No.: 6039  
Op Name: L.D. DRILLING, INC.  
Address: RR 1 BOX 183B 7 SW 26TH AVENUE  
GREAT BEND, KS 67530

Production Casing Size: 4.5 feet: 3388 150 SX CMT  
Surface Casing Size: 8.625 feet: 247 165 SX CMT

*# 110' 18*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/06/2003 9:30 AM

Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.

Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-0395

Proposed  
Plugging  
Method:

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/06/2003 10:30 AM KCC Agent: CASE MORRIS

**Actual Plugging Report:**

Pumped 75 sxs 60/40 pozmix - 10% gel cement down backside.  
Max. P.S.I. 150#. S.I.P. 100#.  
Pumped 185 sxs cement with 600# hulls.  
Max. P.S.I. 400#. S.I.P. 250#.

RECEIVED  
NOV 21 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

*ID*

Signed \_\_\_\_\_

*Case Morris*

(TECHNICIAN)

INVOICED

DATE 11-21-03

INV. NO 2004060811

NOV 17 2003

RAYMOND OIL COMPANY INC  
 ONE MAIN PLACE #1-00  
 WICHITA, KS 67202

#1 DAVIS 5-19-12W  
 C E/2 SE SW

CONTR DUKE DRILLING CO INC CTY BARTON

GEOL ROBERT D. DOUGHERTY FIELD FRANK NORTH

# 1E14 KB CA 10/14/80 CARD ISSUED 4/9/81 IF P 20 BOPD

A.P. 15-009-22,134 LANS 3110-3520 OA

LOG TOPS	DEPTH	DATUM
ANH	645	+1169
E ANH	669	+1145
ELM	2645	- 831
TCP	2722	- 908
PLATTSM	2954	-1120
HEEE	2985	-1171
TOR	3003	-1189
DOUG	3019	-1205
RR LM	3094	-1280
LANS	3107	-1293
B KC	3334	-1520
MARM	3348	-1534
CONG	3355	-1542
ARB	3381	-1567
LTD	3388	-1574
RTD	3390	-1576

8-5/8" 247/165sx, 4 1/2" 3388/150sx

DST (1) 3107-3162/30-60-30-60, GTS  
 19", NO GAUGE, REC 60' O&GCM,  
 60' HC&GCM, 480' GO, 480' MO,  
 SIP 668-680#, FP 113-238/306-375#

DST (2) 3165-3181/15-30-15-30, REC  
 10' M, SIP 34-34#, FP 22-22/  
 22-22#

DST (3) 3245-3272/15-30-60-60,  
 (2ND OPEN) GTS 22", GA 8870 CFG/  
 30", 7940 CFG/45", 6270 CFG/60",  
 REC 15' O&GCM, 300' FROGGY OIL.

RAYMOND OIL COMPANY INC #1 DAVIS 5-19-12W  
 C E/2 SE SW

SIP 736-725#, FP 45-45/68-125#

DST (4) 3273-3327/30-60-30-60, 180'  
 GIP, REC 120' O&GCM, 240' MDY GO,  
 180' FROGGY OIL, SIP 1073-1062#,  
 FP 102-170/215-272#

DST (5) 3381-3390/15-30-15-30, REC  
 5' M, TR FO, SIP 22-22#, FP  
 11-11/11-11#

MICT - CO, PF 4/3110-12, 24/3152-  
 64, 8/3252-56, 16/3276-84, 20/3310-20,  
 AC 2500, SWB LD, POP