

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-093-00616-00-00  
Spot: NENESW Sec/Twnshp/Rge: 14-22S-36W  
2310 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: DIENST Well Number: 1  
County: KEARNY Total Vertical Depth: 2672 feet

Operator License No.: 32787  
Op Name: KANSAS NATURAL GAS OPERATING, I  
Address: PO BOX 818 1200 MAIN STREET  
HAYS, KS 67601

Production Casing Size: 5.5 feet: 3671 WITH 125 SX CMT  
Surface Casing Size: 8.625 feet: 301 WITH 300 SX CMT

*\$ 96<sup>84</sup>*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/20/2003 10:00 AM  
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES  
Proposal Rcvd. from: STEVE LEHNING Company: KANSAS NATURAL Phone: (785) 625-7353

Proposed Plugging Method: PUMP 500# HULLS & 25 SX CMT. PERFORATE & PUMP CMT. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/20/2003 2:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2672'. PERFS AT 2588-2618 & 2648-2662'. PUMPED 500# HULLS & 25 SX CMT. DISPLACED WITH 54 1/2 BBL. MAXIMUM PRESSURE 1000#. SHUT IN PRESSURE 700#. PERFORATED AT 1000'. PUMPED 145 SX CMT. MAXIMUM PRESSURE 1300#. SHUT IN PRESSURE 500#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 50 SX CMT. PUMPED UP TO 400#. BLEW HOLE IN SURFACE PIPE. SHUT DOWN.

RECEIVED  
KANSAS CORPORATION COMMISSION  
NOV 26 2003  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED  
NOV 24 2003  
KCC Dodge City

Signed \_\_\_\_\_

*Kevin D Strube*

(TECHNICIAN)

INVOICED

DATE 12-1-03

NO. 2004060835

*[Signature]*  
Form 01 2/03