

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22647-00-00
Spot: SENW Sec/Twnshp/Rge: 22-32S-11W
1935 feet from N Section Line, 1790 feet from W Section Line
Lease/Unit Name: DONOVAN Well Number: H-1
County: BARBER Total Vertical Depth: 3803 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3799 WITH 100 SX CMT
Surface Casing Size: 8.625 feet: 261 WITH 175 SX CMT
#12360

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/11/2003 1:00 PM

Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: VERNON PLUHAF Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3351

Proposed Plugging Method: SAND BACK TO 3540' WITH 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER
Date/Time Plugging Completed: 11/11/2003 3:30 PM

Witness Type: Plugging Operations Were Not Witnessed
KCC Agent: MICHAEL MAIER

Actual Plugging Report:


PBTD 3786'. PERFS AT 3745-3750'. CIBP @ 3720'. PERF AT 3613'. SAND BACK TO 3540' WITH 5 SX CMT. 1ST PLUG PUMP 10 SX GEL & 50 SX CMT AT 600'. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 15 SX CMT. GOOD CIRCULATION ON JOB.

RECEIVED
NOV 26 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2937' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Michael Maier
(TECHNICIAN)

INVOICED

DATE 12-1-03

INV. NO. 2004060829

[Signature]
FORM 100