

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-21118-00-00
Spot: E2E2NE Sec/Twnshp/Rge: 27-33S-30W
1420 feet from N Section Line, 330 feet from E Section Line
Lease/Unit Name: LANGHOFER Well Number: 1-27
County: MEADE Total Vertical Depth: 5925 feet

Operator License No.: 30129
Op Name: EAGLE CREEK CORPORATION
Address: 150 N. MAIN, STE 905
WICHITA, KS 67202

Surface Casing Size: 8.625 feet: 1718

#192⁵⁶

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/21/2003 7:30 PM
Plug Co. License No.: 30684 Plug Co. Name: ABERCROMBIE RTD, INC
Proposal Rcvd. from: STEVE CRAIG Company: ABERCROMBIE RTD, INC Phone: (316) 262-1841

Proposed Plugging Method: 1ST PLUG AT 1720' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 40 SX CMT. 3RD PLUG AT 40-0' WITH 10 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 11/21/2003 7:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:


1ST PLUG AT 1720' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 40 SX CMT. 3RD PLUG AT 40-0' WITH 10 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 26 2003
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICE.

Plugged through: DP

District: 01



Signed

Steve Durrant

(TECHNICIAN)

INVOICED

DATE 12-1-03
INV. NO. 2004060834