

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23237-00-00  
Spot: E2NW Sec/Twnshp/Rge: 4-12S-15W  
3980 feet from S Section Line, 3340 feet from E Section Line  
Lease/Unit Name: EULERT UNIT Well Number: 1  
County: RUSSELL Total Vertical Depth: 3215 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 4514 COLE AVE., STE 804, LB 30  
DALLAS, TX 75205

Surface Casing Size: 8.625 feet: 736

#10449

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/16/2003 12:00 PM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: BILL WYNN Company: MURFIN DRILLING CO., INC. Phone: (785) 650-9623

Proposed Plugging Method: Order 160 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: ROGER MOSES

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 11/16/2003 10:45 PM

KCC Agent: ROGER MOSES

**Actual Plugging Report:**

1st. Plug at 3089' w/25 sxs cement.  
2nd. Plug at 785' w/100 sxs cement.  
3rd. Plug at 40' w/10 sxs cement.  
15 sxs in rathole.  
10 sxs in mousehole.  
Total of 160 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack - w/8 5/8" wiper plug.

RECEIVED  
NOV 26 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

10

Signed

Regan L. Massey  
(TECHNICIAN)

INVOICED

Form CP-2/3

GATE 12-1-03

NV. NO. 2004060837

NOV 24 2003