

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-00147-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 35-23S-36W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: BENDER Well Number: 1
County: KEARNY Total Vertical Depth: 2800 feet

Operator License No.: 5952 Production Casing Size: 5.5 feet: 2777 WITH 350 SX CMT
Op Name: BP AMERICA PRODUCTION COMPANY Surface Casing Size: 8.625 feet: 765 WITH 350 SX CMT
Address: 2225 WEST OKLAHOMA AVENUE
ULYSSES, KS 67880 #9100

Well Type: GAS UIC Docket No: Date/Time to Plug: 11/18/2003 9:00 AM
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES
Proposal Rcvd. from: JOE EUDEY Company: BP AMERICA Phone: (620) 356-6955

Proposed Plugging Method: CIBP @ 2548'. PERFORATE AT 800'. FILL WITH CMT TO SURFACE.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/18/2003 11:45 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:


PBTD 2800'. PERFS AT 2600-2800'. CIBP @ 2548' WITH 2 SX CMT. PERFORATED AT 800'. PUMPED WATER DOWN 5 1/2" & HAD FULL RETURNS TO SURFACE BETWEEN 8 5/8" X 5 1/2" ANNULUS. PUMPED 200 SX CMT TO SURFACE.

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 26 2003
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL 2% CC BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Kevin D. Strube

(TECHNICIAN)

INVOICE

DATE 12-1-03

IN. NO. 2004060832

Form 8879-
[Signature]