

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21080-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 12-10S-23W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: LAW UNIT Well Number: 405
County: GRAHAM Total Vertical Depth: 4125 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

Production Casing Size: 5.5 feet: 4124 175 SX CMT
Surface Casing Size: 8.625 feet: 198 175 SX CMT

#134⁰⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2003 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: ALLEN BANGERT Company: GLM COMPANY Phone: (785) 483-1676

Proposed Plugging Method: Ordered 300 sxs cement and 500# hulls.
Perforate at 1575' and 1960'.

Plugging Proposal Received By: ROGER MOSES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/20/2003 10:30 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 198' w/175 sxs cement. 5 1/2" casing at 4124' w/175 sxs cement.
12-28-1978 perforated at 960' and circulated with 415 sxs cement.
Tied to 5 1/2" casing and squeezed 230 sxs cement with 500# hulls.
Max. P.S.I. 900#. S.I.P. 400#.
Visual inspection of annulus - cement to surface.

RECEIVED
NOV 26 2003
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS IRWIN #5. ALLIED CEMENTING COMPANY. KELLER TANK-WATER.

Plugged through: CSG

District: 04

110

Signed

Roger Moses
(TECHNICIAN)

INVOICED

DATE 12-1-03

INV. NO. 2004060839

Form CP-2/3

NOV 24 2003

JOHN B. COLLINS #5 IRWIN
 1007 CODY, SUITE A,
 HAYS, KANSAS 67601 CTY GRAHAM
 CONTR DRILLING OIL, INC. FIELD LAW SE
 GEOL LARRY GRAY
 x 2414 KB CM 11/18/78 CARD ISSUED 2/17/79 IP P 37 BOPD & 275
 BWPD,
 LANS 3757-3763

12-10-23W
 NW NW NE

+	+	+
+	+	+

API 15-065-21,080

LOG	TOPS	DEPTH	DATUM
ANH	1952	+ 462	
TOP	3424	-1010	
HEEB	3639	-1225	
TOR	3662	-1248	
LANS	3676	-1262	
BKC	3905	-1491	
MARM	3986	-1572	
CONG	4100	-1686	
LTD	4123	-1709	
RTD	4125	-1711	

8-5/8" 198/175sx, 5 1/2" 4124/175sx

NO DST'S
 MICT - CO, PF 3757-3763, AC 2000 GAL,
 SWB 2430 BFPH (6% O), POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS