

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20222-00-00
Spot: SENW Sec/Twnshp/Rge: 30-8S-35W
3300 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: LAUTERBACH Well Number: 1
County: THOMAS Total Vertical Depth: 4870 feet

Operator License No.: 31514
Op Name: THOROUGHbred ASSOCIATES L.L.C.
Address: 8100 E. 22ND ST. - BUILDING 600
WICHITA, KS 67226

Production Casing Size: 2.875 feet: 755 185 SX CMT
Surface Casing Size: 8.625 feet: 284 200 SX CMT

#158²⁸

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/18/2003 3:00 PM

Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: CINDA SARIA Company: THOROUGHbred ASSOCIATES LL Phone: (316) 685-1512

Proposed Plugging Method: Ordered 125 sxs 60/40 pozmix - 10% gel - 200# hulls.

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 11/18/2003 5:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforations 672' - 686'; 644' - 646'. TD 4870'. PBTd 734'.
8 5/8" surface casing set at 284' w/200 sxs cement. 2 7/8" production casing set at 755' w/185 sxs cement.
Connected to 2 7/8" production casing - pumped 123 sxs cement with 200# hulls.
Max. P.S.I. 1000#. S.I.P. 300#.
Connected to 8 5/8" surface casing - pumped 2 sxs cement.
Max. P.S.I. 300#. S.I.P. 200#.

RECEIVED
NOV 26 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

INVOICED

DATE 12-1-03
INV. NO. 2004060843

NOV 19 2003

ABRAXAS PETROLEUM CORPORATION

P. O. BOX 17485

SAN ANTONIO, TX. 78217

CONTR RAINS & WILLIAMSON OIL CO CTY THOMAS

#1 LAUTERBACH

30-8-55W
C SE NW

GEOL GLENN TARCEY

FIELD WC

E 3343 KB CM 12/22/80 CARD ISSUED 3/19/81 IP SIGW



API 15-193-20,222

NOB 672-686 &
644-646

LOG	TOPS	DEPTH	DATUM
NOB	NA		
SC	2847	+ 496	
HEEB	4127	- 784	
LANS	4168	- 825	
B KC	4462	-1119	
MARM	4506	-1163	
PAW	4590	-1247	
ET SC	4629	-1286	
CHER	4650	-1307	
MISS	4832	-1489	
RTD	4870	-1527	
LTD	4868	-1525	

8 5/8" 284/200sx; 2 7/8" TBG SET/185sx
 DST (1) 4630-4780/30-30-10-20, 10" M
 SIP 1120-1037#, FP 30-30/30-30,
 HP 2465-2439#
 MICT - PBTD 734, PF 56/672-686, 8/644-
 646, FRAC 48,400 CF NITRO F 2250 GAL
 FOAM F 10,000#SD, SI, POT NA

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

010104
