

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20215-00-00
Spot: N2NWSW · Sec/Twnshp/Rge: 26-8S-36W
2310 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: PALMGREN A Well Number: 1
County: THOMAS Total Vertical Depth: 4820 feet

Operator License No.: 31514
Op Name: THOROUGHNBRED ASSOCIATES L.L.C.
Address: 8100 E. 22ND ST. - BUILDING 600
WICHITA, KS 67226

Production Casing Size: 2.875 feet: 822 180 SX CMT
Surface Casing Size: 8.625 feet: 275 200 SX CMT

#15665

Well Type: GAS UIC Docket No: Date/Time to Plug: 11/18/2003 1:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: CINDA SARIA Company: THOROUGHNBRED ASSOCIATES LL Phone: (316) 685-1512

Proposed Plugging Method: Ordered 125 sxs 60/40 pozmix - 10% gel - 200# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/18/2003 2:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforations 768' - 783'. TD 4820'. PBTB 862'.
8 5/8" surface casing set at 275' w/200 sxs cement. 2 7/8" production casing set at 822' w/180 sxs cement.
Connected to 2 7/8" production casing - pumped 123 sxs cement with 200# hulls.
Max. P.S.I. 600#. S.I.P. 300#.
Connected to 8 5/8" surface casing - pumped 2 sxs cement.
Max. P.S.I. 300#. S.I.P. 200#.

RECEIVED
NOV 26 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

12-1-03

NY. NO.

2004060843

NOV 19 2003

ABRAXAS PETROLEUM CORP
 P.O. BOX 17485
 SAN ANTONIO, TX 78217
 CONTR RAINS & WILLIAMSON

#1 PALMGREN #1 26-8-36W
 N/2 NW SW


CTV THOMAS

GEOL GLENN TRACEY FIELD WC (1/4 NE OF STUDER)

3400 KB CM 11/22/80 CARD ISSUED 3/19/81 IP SIGW

API 15-193-20,215

NIOB 768-83



LOG	TOPS	DEPTH	DATUM
NIOB		NA	
B KC		4498	-1098
MARM		4548	-1148
PAW		4626	-1226
FT SC		4668	-1268
CHER		4688	-1288
RTD		4820	-1420
LTD		4790	-1390

8 5/8" 275/200sx; 2 7/8" TBG SET 822'
 NO DSTS
 MICT - PF 768-783, FRAC 46,000SCF
 NITROGEN + 4,000GAL GEL WTR +
 10,000#SD, K.O., SIGW, POT NA

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS