

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20141-00-00
Spot: NESENW Sec/Twnshp/Rge: 17-9S-19W
3630 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: STULL Well Number: 4
County: ROOKS Total Vertical Depth: 3554 feet

Operator License No.: 31430
Op Name: WHITE EAGLE RESOURCES CORP.
Address: PO BOX 270948
LOUISVILLE, CO 80027

Production Casing Size: 7 feet: 3544 w/125 sxs cmt
Surface Casing Size: 10.75 feet: 256 w/185 sxs cmt

#115^{SI}

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2003 3:30 PM

Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: RANDY WEIGEL Company: WHITE EAGLE RESOURCES CORP. Phone: (785) 434-4900

Proposed Plugging Method: Ordered out 320 sxs 60/40 pozmix - 10% gel - 500# hulls - 11 sxs gel spacer.
Squeezed 12-11-1992 - 1040' - 1054' w/200 sxs cement.
Fluid level 300' from surface. PBTB 3370'. LKC Perfs 3273' - 3347'.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/20/2003 7:00 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3255'. Allied pumped 11 sxs gel spacer with 100# hulls,
followed with 50 sxs 60/40 pozmix - 10% gel with 200# hulls.
Pulled to 2100'. Allied pumped 240 sxs cement with 200# hulls - cement circulated.
PTOH. Squeezed with 30 sxs cement.
Max. P.S.I. 500#. S.I.P. 200#.
Hooked on to backside - instant 500#.

RECEIVED
NOV 26 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 12-1-03
INV. NO. 2004060845

Form CP-2/3

ND

NOV 21 2003

