

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21354-00-01
Spot: NWSENW Sec/Twnshp/Rge: 28-18S-17W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: HOLOPIREK Well Number: 1
County: RUSH Total Vertical Depth: 3778 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

Production Casing Size: 4.5 feet: 3778 WITH 75 SX CMT
Surface Casing Size: 8.625 feet: 891 WITH 400 SX CMT

#122 79

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/13/2003 11:55 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: VERNON Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: SAND OFF TO 3670' WITH 5 SX CMT. RUN TUBING TO 1100'. PUMP CMT. PERFORATE AT 850'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: JIM HOLLAND WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/13/2003 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:


PERFS AT 3722-24'. SANDED TO 3673' WITH 4 SX CMT. PUMPED 15 SX COMMON CMT WITH 3% CC AT 1100'. WAITED 1 1/2 HOURS. PRESSURED CASING . HELD AT 500#. PERFORATED @ 850' & PUMPED 170 SX CMT. DID NOT CIRCULATE. SHUT IN WITH 100#. TIED ONTO BACKSIDE & PUMPED 80 SX CMT. SHUT IN WITH 200#.

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 26 2003
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND CEMENTING. NO CASING RECOVERED.

Plugged through: TBG

District:



Signed

Michael Maier
(TECHNICIAN)

INVOICED

DATE 12-1-03
INV. NO. 2004060831

Form 2/3