

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-00778-00-01  
Spot: SENW Sec/Twnshp/Rge: 2-10S-25W  
3300 feet from S Section Line, 3300 feet from E Section Line  
Lease/Unit Name: BERNARD Well Number: 1  
County: GRAHAM Total Vertical Depth: 4257 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

Production Casing Size: 4.5 feet: 3880  
Surface Casing Size: 8.625 feet: 190 *138<sup>35</sup>*

Well Type: SWD UIC Docket No: D17675.0 Date/Time to Plug: 10/23/2003 11:00 AM

Plug Co. License No.: 32970 Plug Co. Name: H-D OIL FIELD SERVICE, INC.

Proposal Rcvd. from: MARK LEIKER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 400 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/23/2003 2:45 PM

KCC Agent: ROGER MOSES

**Actual Plugging Report:**

8 5/8" S.P. at 190' w/130 sxs cement. 4 1/2" casing at 3880' w/150 sxs cement.  
Circulated from 1895' to surface with 200 sxs cement, *with DV Tool.*  
Ran tubing to 1664' - circulated with 85 sxs cement and 300# hulls. Max. P.S.I. 700#.  
Pulled all tubing - circulated down 4 1/2" and up thru hole in casing thru 8 5/8" S.P. with 110 sxs cement.  
Shut in 8 5/8" - squeezed 205 sxs cement.  
Max. P.S.I. 300#. S.I.P. 200#.

RECEIVED  
NOV 03 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. PFEIFER DOZER-WATER.

Plugged through: TBG

District: 04

Signed

*Roger L. Moses*  
(TECHNICIAN)

INVOICED

DATE 11-3-03

INV. NO. 2004060723

Form CP-2/3 ✓

OCT 29 2003

WADICEN

KIMBARK EXPLORATION

#1 BERNARD

2-10-25W  
C SE NW

Contr. KIMBARK EXPL

County

E 2518RB Comm

Comp

11-6-59

IP

150 BOPD

PHY POT

Tops	Depth	Datum
HEEB	3760	-1242
TOR	3780	-1262
LANS	3798	-1280
B/KC	4033	-1515
CHERO	4229	-1711
TD	4257	-1739

Casing 8" 190 4" 3880  
 DST 3790-3805/30", 25' M, SSO,  
 BHP 1255#  
 DST 3815-35/1 HR, 90' G, 90' O &  
 GCM, 670' O, 515' W, BHP 1230#  
 DST 3830-45/1 HR, 185' M & W, 1165#  
 DST 3920-40/30", 30' MUD, BHP 0#  
 DST 3945-65/30", 20' M, BHP 0#  
 DST 3990-4000/30", 10' M, BHP 0#  
 PERF 18/3827-30: 2850' FIH/12 HR  
 1250' O, 1600' W: SWB 4 BO & 6 BWPH



(POWELL & RUWWE, GEO.)

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS