

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-02988-00-01 <sup>102</sup>  
Spot: SWSESE Sec/Twnshp/Rge: 23-9S-22W  
330 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: IRONCLAD Well Number: 2  
County: GRAHAM Total Vertical Depth: 3782 feet

Operator License No.: 3007 101 STATE OF KS  
Op Name: WEST X, INC. Fee Fund  
Address: PO BOX 126  
HAYS, KS 67601

Production Casing Size: 5.5 feet: 3782  
Surface Casing Size: 8.625 feet: 240

Well Type: SWD UIC Docket No: D25219.0 Date/Time to Plug: 11/07/2003 9:00 AM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 175 sxs 60/40 pozmix - 10% gel - 400# hulls.  
DV at 1889' set with 350 sxs cement.  
CIBP at 1900'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/07/2003 11:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 5 1/2" - mixed and pumped 150 sxs cement with 400# hulls.  
Max. P.S.I. 400#.  
Hooked up to the annulus and pumped 20 sxs cement.

THIS IS A KCC FEE FUND PLUGGING.

RECEIVED

NOV 18 2003


WICHITA

Remarks: LEASE ALSO KNOWN AS HOLZHAUER A-2. ALLIED CEMENTING COMPANY.

Plugged through: CSG


District: 04

Signed



(TECHNICIAN)

11-131 Map No. \_\_\_\_\_, O W W O  
 OPER. CITIES SERVICE OIL CO. - Wichita,  
 Ks.  
 WELL #202-W TRONCLAD UNIT  
 CONTR. \_\_\_\_\_



S-T-R 23-9S-22W  
 SPOT SW SE SE  
 CO GRAHAM (Ks)  
 ELEV 2343 KB

FIELD Tronclad Field (Lans) (Old Spl's:)  
 I.P. Wtr Input Well 3554-3737 - Lans Anh 1826 / 517  
 Hb 3515 -1172

OLD INFO: (Was CSO #2 Holzhauser "A") (Spd 6-16-54 8" @240')  
 DST #1 (Lans) 3555-74, Op 60", R 10' HOCM / 30' SOCMW, FSIP Dodge 3535 -1192  
 600# Lans 3551 -1208  
 DST #2 (Lans) 3594-3621, Op 60", R 2' oil, 30' SOCM & SW / OTD 3782 -1439  
 150' SW, FSIP 670#

DST #3 (Lans) 3688-3700, Op 30", R 32' M, FSIP 400#  
 DST #4 (Lans) 3729-40, Op 60", R 11' M, FSIP 900#, OTD 3782  
 5 1/2" @3782' w/cem - CO 3763, 33/3728-37 no fluid, 23/3693-  
 99 (Lans) 1500A, 5' ld, Pump 88 BW/16 hrs, PB 3631, 39/3591-  
 3601 & 23/3554-62 (Lans) 2000A, Rec ld, POP, Co P 16 BO /  
 123 BW/24 hrs, State Pot: 27 BOPD / 143 BW/24 hrs, Lans  
 3554-3601, PBTD 3631, Completed 7-28-54 - Temp Abdn

NEW INFO: (2-26-64)  
 (Convert to wtr input well), MICT, CO, Drove BP down & CO  
 to 3761, tbg 3540 (all old Perfs open) No Acid, Water Input  
 Well (3554-3737) Lans - FIRST REPORTED & COMPLETED on 11-11-  
 65

*Data Inc.*

CITIES SERVICE #2 HOLZHAUER 'A' 23-9-22W SW SE SE

Contr. \_\_\_\_\_ GRAHAM County

E 2343 Comm. \_\_\_\_\_ Comp. 7-30-54 IP 27 BOPD & 143 BW

Tops	Depth	Datum	Casing
			5" 3782
			PERF 3728-37: 3693-99: ACID
			500: PB 3631: PERF 3591-
DODGE	3510	-1197	3601: 3554-62: ACID 2000:
			PMP 21 BO & 134 BW/24 HRS
			PMP 15 BOPD: 65 BW/10 HRS
LANS	3555	-1212	