

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

RECEIVED
NOV 19 2003

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

KCC WICHITA

Lease Operator: Bear Petroleum, Inc.

Address: Box 438, Haysville, Ks. 67060

Phone: (316) 524-1225 Operator License #: 4419

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: November 11th, 2003 (Date)

by: Mike Maier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: 3722' Bottom: 3778' T.D. 3778'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 165-21354-0001

Lease Name: Holopirek

Well Number: 1

Spot Location (QQQQ): _____ - NW - SE - NW

3630 Feet from North / South Section Line

3630 Feet from East / West Section Line

Sec. 28 Twp. 18 S. R. 17 East West

County: Rush

Date Well Completed: 11-6-1997

Plugging Commenced: November 12, 2003

Plugging Completed: November 13, 2003

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	891'	8-5/8"	891'	0'
	Production	0'	3778'	4-1/2"	3778'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

M.I.R.U. Ran bailer to bottom. Sand off bottom to 3670'. Put 4 sacks of cement on top. Run in the hole with 1100' of 2-3/8" workstring. Pumped 15 sacks - 3% calcium plug. Let set for 1-1/2 hours. Pressured up on casing to 400# - good. Rigged up wireline and perforated @ 850'. Pumped 180 sacks down casing and 70 sacks down backside. Rigged down service companies. Left 200# pressure on surface pipe. Rigged down and moved off.

Name of Plugging Contractor: D.S.&W. Well Servicing, Inc. License #: 6901

Address: P.O. Box 231, Claflin, Ks. 67525

Name of Party Responsible for Plugging Fees: Bear Petroleum, Inc.

State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt Expires 4/13/06

(Signature) Edward S. Nemnich
(Address) P.O. Box 231, Claflin, KS 67525

SUBSCRIBED and SWORN TO before me this 17th day of November, 20 03

Karen J. Mitchell
Notary Public

My Commission Expires: 4/13/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202