

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202 TYPE OR PRINT

WELL PLUGGING RECORD

K.A.R.-82-3-117

15-167-05159-00-00
API NUMBER 15 5/28/48

RECEIVED

LEASE NAME Tittler A

WELL NUMBER 6

NOV 19 2003

~~330'~~ S 4950 Ft. from 5 Section Line

~~330'~~ E 4950 Ft. from E Section Line

NOTICE: Fill out completely
and return to Cons. Div.

KCC WICHITA

office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc.

SEC 12 TWP. 15S RGE. 14W (E) or (W)

ADDRESS 250 N. Water, Ste. 300

COUNTY Russell

Wichita, KS 67202

PHONE # 267-3241 OPERATORS LICENSE NO. 30606

Date Well Completed 5/28/48

Character of Well Oil (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging commenced 10/30/03

Plugging Completed 10/30/03

The plugging proposal was approved on 10/30/03
(date)

By Jay Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation ARB Depth to Top 3320' Bottom 3325' TD 3325' Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	525' <u>523'</u>	8 5/8"	525' <u>523'</u>	
		Prod.	3320'	5 1/2"	3320'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. RU Perf-Tech perforate @1500' 2 spf, 950', 430' 2 spf, TIH w/53 jts 2 3/8" tbg @ 1610', RU Allied Cementing mix & pump 75 sx 60/40 10% gel & 400# hulls, pull 30 jts to 800', pump 80 sx cement circ to surface up 8 5/8" shut in. Swage casing & pump 25 sx cement shut in @ 250#.

Name of Plugging Contractor Murfin Drilling Co., Inc. License No. 30606

Address 250 N. Water, Ste. 300 Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.



(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J. K. Pfeifer
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this _____ day of ..

Notary Public - Barbara J. Dodson
My Commission Expires: 12-16-03

Form CP-4 Revised 05-88



RECEIVED
 NOV 19 2003
 KCC WICHITA

WELL RECORD

Lease Tittel "A" Well No. 6 S. 12 T. 15 R. 14W
 County Russell State Kansas Elev. 1875 (1873 Gr)
 Location 330' South and 330' East of NW Corner
 Dr. Commenced May 16, 1948 Dr. Completed May 28, 1948
 Drilled By Holm Drilling Company T. D. 3325'; P.B.T.D. 3290'
 Acid 4000 gals. (see below)
 Initial Prod. Physical: 350 oil, 15 water, 2 1/2 hrs. (6-15-48)

Casing Record	
8-5/8" @	523' cem. 250 sx cem. and 3 sx C. C.
5-1/2" @	3320' cem. 275 sx cem.
Top Topeka	2770'
Top Lansing	3061'
Top Arbuckle	3319'
Penetration	6'
Total Depth	3325'
Fillup:	80' oil in 1 hr. 10 mins.
	110' oil in 1 hr. 35 mins.
	300' oil in 2 hrs. 35 mins.
	485' oil in 3 hrs. 35 mins.
	635' oil in 4 hrs. 35 mins.
	780' oil in 7 hrs. 35 mins.
	1670' oil in 20 hrs.
Set Lane-Wells plug at 3300'. Dumped 1 sack cement on top plug; top cement 3290 SIM.	
Perf. 63 shots 3142-60	
Perf. 20 shots 3088-96	
Perf. 12 shots 3099-3102	
6-11-48 Acidized 3000 gals. 3142-60	
6-13-48 Acidized 1000 gals. 3088-3102	
SYFO:	500' 0°
	1000' 0°
	1500' 1°
	2000' 1°
	2500' 1°
	3000' 1°

Geol. 16A
 AM 3-48

ALLIED CEMENTING CO., INC. 12853

Federal Tax I.D. [REDACTED]

WF

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Crest Bend

DATE <u>10-30-03</u>	SEC. <u>12</u>	TWP. <u>15</u>	RANGE <u>14 W</u>	CALLED OUT <u>8:00 am</u>	ON LOCATION <u>10:00 am</u>	JOB START <u>10:30 am</u>	JOB FINISH <u>12:15</u>
LEASE <u>Title</u>				WELL# <u>A-#6</u>	LOCATION <u>North on 281 - just before new</u>	COUNTY <u>Russell</u>	STATE <u>KS</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)				<u>river bridge - East 1/2 miles - North into</u>			

CONTRACTOR <u>Murfin Dalg</u>	OWNER <u>Murfin Dalg</u>
TYPE OF JOB <u>Old hole plug</u>	
HOLE SIZE <u>10"</u>	CEMENT
CASING SIZE <u>2 1/2</u>	AMOUNT ORDERED <u>350 5x 6 1/4 10 1/2 gal</u>
TUBING SIZE <u>2"</u>	<u>& 200 lbs of bulls on side</u>
DRILL PIPE	<u>used - 100 5x cement & 200 lbs of bulls</u>
TOOL	
PRES. MAX <u>270</u>	COMMON <u>10 Bag</u> @ <u>7.15</u> <u>772.20</u>
MEAS. LINE	POZMIX <u>72 Bag</u> @ <u>3.00</u> <u>273.60</u>
CEMENT LEFT IN CSG.	GEL <u>14 Bag</u> @ <u>10.00</u> <u>140.00</u>
PERFS.	CHLORIDE @
DISPLACEMENT	<u>Hulls 5000</u> @ <u>18.00</u> <u>90.00</u>

EQUIPMENT			
PUMP TRUCK	CEMENTER <u>Jack</u>		
# <u>620</u>	HELPER <u>J.D.</u>		
BULK TRUCK		HANDLING <u>385 Bag</u> @ <u>1.15</u> <u>442.75</u>	
# <u>344</u>	DRIVER <u>Steve</u>	MILEAGE <u>385 Miles</u> @ <u>10</u> <u>3850.00</u>	
BULK TRUCK			
#	DRIVER <u>tax - state man</u>		
		TOTAL	<u>1911.05</u>

REMARKS:
1st plug @ 1600' with 75 5x cement
+ 400 lbs of bulls -
2nd plug @ 800' with 80 5x cement
+ 100 lbs of bulls - full tubing -
swedge 500 & mix 25 5x cement - shut
in @ 200 lbs -

Thanks

SERVICE	
DEPTH OF JOB <u>1600</u>	
PUMP TRUCK CHARGE	<u>475.00</u>
EXTRA FOOTAGE @	
MILEAGE <u>10</u> @ <u>3.80</u>	<u>38.00</u>
PLUG @	

CHARGE TO: Murfin Dalg

STREET _____

CITY _____ STATE _____ ZIP _____

RECEIVED
 NOV 19 2003
 KCC WICHITA

TOTAL 510.00

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Mark Adlan

_____ @ _____	
_____ @ _____	
_____ @ _____	
_____ @ _____	
_____ @ _____	
TOTAL _____	
TAX _____	
TOTAL CHARGE _____	
DISCOUNT _____	IF PAID IN 30 DAYS
_____	PRINTED NAME