

RECEIVED

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form CP-4

September 2003

Type or Print on this Form

Form must be Signed

All blanks must be Filled

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
30 days from plugging date.

NOV 19 2003  
KCC WICHITA

WELL PLUGGING RECORD  
K.A.R. 82-3-117

Lease Operator: American Energies Corporation

Address: 155 N. Market, #710, Wichita, Ks. 67202

Phone: (316) 263-5785 Operator License #: 5399

Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: November 9th, 2003 (Date)

by: Steve Durant (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

\_\_\_\_\_ Depth to Top: 3613' Bottom: 3786' T.D. 3803'

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-007-226470000

Lease Name: Donovan H

Well Number: #1

Spot Location (QQQQ): \_\_\_\_\_ - NW - SE - NW

1935 Feet from  North /  South Section Line

1790 Feet from  East /  West Section Line

Sec. 22 Twp. 32 S. R. 11  East  West

County: Barber

Date Well Completed: 5/2/2001

Plugging Commenced: 11/10/03

Plugging Completed: 11/11/03

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	261'	8-5/8"	261'	0'
	Production	0'	3799'	5-1/2"	3799'	<del>2037-80'</del> 2938

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

M.I.R.U. Run to bottom with tool. Cast Iron Bridge Plug @ 3720'. Perforations were @ 3613'. Sand off. Plug back total depth @ 3540'. Spot 5 sx cement on top. Set jacks and pull stretch into pipe. Run in with knife - cut @ 2937'. Pull out of hole with casing. Pulled to 650' - spot 10 sx gel - 50 sx cement; pulled to 270' - spot 50 sx cement; pulled to 40' - spot 25 sx cement and circulated to surface. Tore down jacks and rig, and moved off.


Name of Plugging Contractor: D.S.&W. Well Servicing, Inc. License #: 6901

Address: P.O. Box 231, Claflin, Ks. 67525

Name of Party Responsible for Plugging Fees: American Energies Corporation

State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

 **KAREN J. MITCHELL**  
Notary Public - State of Kansas  
My Appt Expires 4/13/06

(Signature) Edward S. Nemnich

(Address) P.O. Box 231, Claflin, Ks. 67525

SUBSCRIBED and SWORN TO before me this 17th day of November, 20 03

Karen J. Mitchell My Commission Expires: 4/13/06  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202