

RECEIVED
 NOV 14 2003
 KCC WICHITA

LEASE NAME Pfeifer

WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely and return
 to Cons. Div. office within 30 days.

990 Ft. from CP 2/3 Line of Section (circle one)
2310 Ft. from CP 2/3 Line of Section (circle one)

LEASE OPERATOR White Eagle Res

SPOT LOCATION SE - NE - NW

ADDRESS P.O. Box 187

SEC. 19 TWP. 13 S. RGE 19 or (W)

CITY, STATE, ZIP Plainville Ks 67663

COUNTY Ellis

PHONE# (785) 737-3736 OPERATORS LICENSE NO. 31430

Date Well Completed 3/31/64

Character of Well O:1
 (Oil, Gas, D&A, SMD, Input, Water Supply Well)

Date Plugging Commenced 9-29-03

Date Plugging Completed 9-29-03

The plugging proposal was approved on 9-23-03 (date)

by Jay Pfeifer / Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation(s) Toronto L-KC A B F I J K Depth to Top 3463 Bottom 3693 T.D. 3899

Show depth and thickness of all water, oil and gas formations.

3890
per 2/2/03

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
		0	198	8 5/8		0
		0	3880	5 1/2		0

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 0 feet to 2100 feet each set.

Ran 2 3/8 to bottom. Started out at 1,950'. Circ hole and got tubing down to 2,100'
Allied Cementing pumped 50 sxs 60/40 10% gel + 200# hulls. Pulled tubing to 250' &
pumped 130 sxs of 60/40 cement w/ 10% gel + 300# hulls. Cement circ. Pull tubing
out of hole. Pumped 10 sxs of 60/40 10% gel. Max pressure 800#. S.I. pressure 800#
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing / Express Well Service

License No. 10426

Address E.W.S. = P.O. Box 19 Victoria, Ks. 67671

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: White Eagle Resources

STATE OF Colorado COUNTY OF Boulder, ss.

Randy Weigel (Employee of Operator or (Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Randy Weigel

(Address) P.O. Box 187 Plainville Ks 67663

SUBSCRIBED AND SWORN TO before me this 13th day of November, 2003

S. J. Stahl
 Notary Public

My Commission Expires: 03-05-06

