

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

RECEIVED KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

NOV 03 2003

Lease Operator: KCC WICHITA Coronado Oil & Gas, Inc. Address: P.O. Box 1285, Great Bend, Kansas 67530 Phone: (620) 792-6702 Operator License #: 6141 Type of Well: D&A Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR) The plugging proposal was approved on: 10-15-03 by: Hays Is ACO-1 filed? [X] Yes [] No Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D. 3285

API Number: 15 - 159-00415-0000 Lease Name: Janssen C Well Number: 4 Spot Location (QQQQ): SE SW SE 330 Feet from [] North / [X] South Section Line 1650 Feet from [X] East / [] West Section Line Sec. 2 Twp. 18S S. R. 7 East [] West County: Rice Date Well Completed: 10-15-03 Plugging Commenced: 10-15-03 Plugging Completed: 10-15-03

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Handwritten entries show casing from 0 to 235' and 236' with size 8 5/8" and put in 235' and 236'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged with 160 sacks 60/40 Poz., 4% Gel. 1st. plug - 35 sacks @ 1050', 2nd. plug - 35 sacks @ 600', 3rd. plug - 35 sacks @ 280', wiper plug - 30 sacks to surface, rathole - 15 sacks, mousehole - 10 sacks.


Name of Plugging Contractor: Allied Cementing Company, Inc. License #: 9431 / 9996 Address: P.O. Box 31, Russell, Kansas 67665

Name of Party Responsible for Plugging Fees: Coronado Oil & Gas, Inc. State of Kansas County, Barton, ss.

Steve Bodine (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Steve W. Bodine (Address) P.O. Box 1285, Great Bend, Ks. 67530

SUBSCRIBED and SWORN TO before me this 27 day of October 2003 by Tonni L. Bodine Notary Public My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials and signature at bottom right.