

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-01505 -00-00  
Bragg  
LEASE NAME \_\_\_\_\_

RECEIVED

NOV 17 2003

KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 3  
3300 Ft. from (S) Section Line  
1650 Ft. from (E) Section Line

LEASE OPERATOR Great Eastern Energy & Development  
ADDRESS 550 W. Texas, Midland, Tx 79702

SEC. 33 TWP. 9 RGE. 21 (E) or (W)  
COUNTY Graham

PHONE# 432, 6-2-1178 OPERATORS LICENSE NO. 9449

Date Well Completed 11-24-54

Character of Well Oil

Plugging Commenced 9-4-03

(Oil, Gas, D&A, SWD, Input, Water Supply Well)  
9-4-03

Plugging Completed 9-4-03

The plugging proposal was approved on \_\_\_\_\_ (date)  
by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3853 Bottom 3858 T.O. 3858

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	oil	3853	3858	8 5/8	200	CP-2/3
				5 1/2	3853	
					3853	CP 2/3 0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set  
Perf 2250 - 1800 - 1050, Pmped 5 sks gel spacer followed w/ 40 sks  
60/40 poxmix-10% gel w/ 100 # hulls, Pmped 100 sks cmt w/ 400 # hulls  
cmt circulated. Squeezed w/ 80 sks. Max psi 500 # slp 300#. Pressure 30  
Backside 200#

Name of Plugging Contractor Allied Cementing License No. 99996

Address P.O. Box 31, Russell, Ks 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Great Eastern Energy & Development

STATE OF Kansas COUNTY OF Graham, ss.


Bill Robinson (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 5 day of November, 2003



Gwynna Crow  
Notary Public

My Commission Expires: 1/20/04

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01505-00-00  
Spot: E2SWNE Sec/Twnshp/Rge: 33-9S-21W  
3300 feet from S Section Line. 1650 feet from E Section Line  
Lease/Unit Name: BRAGG Well Number: 2  
County: GRAHAM Total Vertical Depth: 3858 feet

Operator License No.: 9449  
Op Name: GREAT EASTERN ENERGY & DEV. CO  
Address: 550 W. TEXAS STE 660  
MIDLAND, TX 79703

Production Casing Size: 5.5 feet: 3853  
Surface Casing Size: 8.625 feet: 210

Well Type: Oil UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/04/2003 10:30 AM

Plug Co. License No.: 92926 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Revd. from: MIKE DAVINSON Company: GREAT EASTERN ENERGY & DEV. Phone: (785) 623-7520

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls - 18 sxs gel spacer.  
No squeeze records. Perforate at 2250' - 1800' - 1050'.

Plugging Proposal Received By: LUKE DEJNES  
Date/Time Plugging Completed: 09/04/2003 2:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Log Tech hit bridge at 690'.  
Run tubing to cleaned out 2685'. PTOH.  
Perforated 2250' - 1800' - 1050'.  
Run tubing to 2600'.  
Allied pumped 5 sxs gel spacer, followed with 40 sxs 60/40 pozmix - 10% gel with 100# hulls.  
Pulled tubing to 1500'.  
Allied pumped 100 sxs cement with 400# hulls - cement circulated.  
PTOH. Squeezed 80 sxs cement.  
Max. P.S.I. 500#. S.I.P. 300#.  
Hooked up to backside - pressured 200#. Blew hole in 8 5/8" - hole full.

RECEIVED  
NOV 17 2003  
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS DEYOUNG #3. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_  
(TECHNICIAN)

Form CP-2/3

EP 05 2003

