

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 501 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-02-3-117

API NUMBER 15-155-21,339-00-00

LEASE NAME Gagnebin Gas Unit

WELL NUMBER 2

2165 Ft. from S Section Line

1505 Ft. from E Section Line

SEC. 11 TWP. 24S RGE. 9W (E) or (W)

COUNTY Reno

Date Well Completed 01-16-1995

Plugging Commenced 10-3-03

Plugging Completed 10-10-03

RECEIVED
 NOV 05 2003
 KCC WICHITA

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR CORSAIR ENERGY, LC.

ADDRESS 914 E. Douglas, Wichita, Kansas, 67202

PHONE (316) 267-7779 OPERATOR'S LICENSE NO. 50585058

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

A plugging proposal was approved on _____ (date)

Jack Luthi (KCC District Agent's Name).

ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3910'

Show depth and thickness of all water, oil and gas formations.

WELL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	186'	None
				5-1/2"	3899'	2440'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from _____ feet to _____ feet each sack. Plugged off bottom with sand to 3650' and 5 sacks cement. Cut pipe loose @2440', pulled up to 1400', pumped 35 sacks cement and 100% hulls, pulled up to 850', pumped 35 sacks cement and 100% hulls, pulled up to 250' and circulated 115 sacks cement, 60/40 pos. 4% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Corsair Energy, LC.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

do hereby certify that the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances stated herein, and that the statements and matters herein contained and the log of the above-described well as filed therewith are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 4th day of November, 2003

[Signature]
 Notary Public

My Commission Expires:

