

RECEIVED
NOV 14 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

LEASE NAME Pfeifer

WELL NUMBER 7

330 Ft. from S(N) Line of Section (circle one)

2310 Ft. from E(W) Line of Section (circle one)

SPOT LOCATION NE - NE - NW -

SEC. 19 TWP. 13 S. RGE 19 (N) or (W)

COUNTY Ellis

Date Well Completed 4-29-80

Date Plugging Commenced 9-29-03

Date Plugging Completed 10-20-03

LEASE OPERATOR White Eagle Resources

ADDRESS P.O. Box 187

CITY, STATE, ZIP Plainville, Ks. 67663

PHONE#(785) 232-3736 OPERATORS LICENSE NO. 31430

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-23-03 (date)

by Herb Deines / Jay Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation(s) Taranta L-KC BIK + Perm-Chert Depth to Top 3447 Bottom 3765 T.D. 3833

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
		0	207	8 5/8	-	0
		0	3877	5 1/2	-	0

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 0 feet to 3750 feet each set.

9-29-03 Pumped instant pressure on Annular. Ran tubing to 2100' pumped 100 sxs cement w/ 500# hulls. Pulled tubing to 1000' & pumped 125 sxs cement. 9-30-03. Ran tubing to 2000' pumped 100 sxs w/ 500# hulls. Pull tubing to 1000' pumped 80 sxs w/ 500# hulls. SD. 10-20-03 Ran tubing to ~~2000'~~ 1013'. Pump cement. Pumped 75 sxs w/ 50# hulls. Cement circ. Pull tubing and top well off w/ 15 sxs.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing / Express Well Service

License No. 6426

Address EWS - P.O. Box 19 Victoria Ks 67671

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: White Eagle Resources

STATE OF Colorado COUNTY OF Boulder, ss.

Randy Weigel (Employee of Operator or (Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Randy Weigel

(Address) P.O. Box 187 Plainville Ks 67663

SUBSCRIBED AND SWORN TO before me this 13th day of November, 19 2003

A. J. Stahl
Notary

My Commission Expires: 03-05-06

