

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

330 Ft. from 5 Line of Section (circle one)

290 Ft. from 5 Line of Section (circle one)

Per
4/13

SPOT LOCATION NW - NW - NE

SEC. 19 TWP. 13 S. RGE 19 or (W)

COUNTY Ellis

Date Well Completed 10/79

Date Plugging Commenced 9-30-03

Date Plugging Completed 10-20-03

EASE OPERATOR White Eagle Resources

ADDRESS P.O. Box 187

CITY, STATE, ZIP Plainville, Ks. 67663

PHONE#(785) 737-3736 OPERATORS LICENSE NO. 31430

Character of Well OIL
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-23-03 (date)

by Jay Pfeifer / Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation(s) Toronto LKC BFKJ Morningson Depth to Top 3466 Bottom 3782 T.D. 3884

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
		0	224	8 5/8		Ø
		0	3882	5 1/2		Ø

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 0 feet to 3675 feet each set.

9-30-03 Pumped pressure down 8 5/8 casing to 500#. Pumped down 5 1/2 casing w/ 270 sxs 60/40 cement w/ 10% gel + 500# hulk. Max pressure 600#. Well was on very slight vac. Run wireline next day, TOC at 360'. 10/20/03 Put in 30 sxs of 60/40 pm w/ 10% gel. Flushed out top 8' to cut off head. Cement remained at top of well.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing / Express Well Service

License No. -16426

Address EWS = PO Box 19 Victoria Ks 67671

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: White Eagle Resources

STATE OF Colorado COUNTY OF Boulder, ss.

Randy Weigel (Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Randy Weigel

(Address) P.O. Box 187 Plainville, Ks 67662

SUBSCRIBED AND SWORN TO before me this 13th day of November, 19 2003

S. J. Stahl
Notary

My Commission Expires: 03-05-06

