

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,825-0000

LEASE NAME Mildred Unit

WELL NUMBER 1

1,930 Ft. from ^N Section Line

140 Ft. from ^W Section Line

SEC. 13 TWP. 16 RGE. 28 (E) or (W)

COUNTY Lane

Date Well Completed 11-13-03

Plugging Commenced 11-13-03

Plugging Completed 11-13-03

NOV 19 2003

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR Carmen Schmitt, Inc.

ADDRESS Box 47, Great Bend, KS 67530

PHONE# (620) 793-5100 OPERATORS LICENSE NO. 6,569

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-13-03 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4,600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	219'	Cmtd. w/160 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from foot to foot each Push plug to 2,150', pump 50 sax cement on plug thru drill pipe; push plug to 1,330' pump 80 sax cement on plug thru drill pipe; push plug to 650', pump 40 sax cement on plug thru drill pipe; push plug to 250', pump 40 sax cement on plug thru drill pipe; push plug to 40', dump 10 sax cement on plug to cellar; dump 15 sax cement down rat hole and 10 sax down mouse hole

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Carmen Schmitt, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas.


Contractor (Employee of ~~Operator~~) or ~~Operator~~ above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) PO Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 17th day of November, 2003

My Commission Expires:



Ruth Phillips
Notary Public




RECEIVED
 NOV 19 2003
 KCC WICHITA

Shields
 WELL LOG

15-101-21825-0000
 Russell, Kansas

Operator: Carmen Schmitt, Inc.
 Well: Mildred Unit #1
 Commenced: November 1, 2003
 Completed: November 13, 2003
 Contractor: Shields Drilling Co.

Well Description: 1,930' FNL; 140' FWL
 Sec. 13-16S-28W
 Lane Co., KS



CASING RECORD

Size	Run	Pulled
8 5/8"	219'	Cmtd. w/160 sax

Elevation: 2,710' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Sand & shale	2,119'	
Anhydrite	2,156'	
Shale	3,710'	
Shale & lime	4,273'	
Lime	4,425'	
Lime & shale	4,600'	RTD

Notes