

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

NOV 25 2003

Form CP-4 September 2003

WELL PLUGGING RECORD K.A.R. 82-3-117

KCC WICHITA

Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Kansas Natural Gas Operating, Inc. Address: P.O. Box 815 Sublette, Kansas 67877 Phone: (620) 675-8185 Operator License #: 5269 Type of Well: Gas - Hugoton Docket #: N/A The plugging proposal was approved on: November 20, 2003 by: Kevin Straub Strube Is ACO-1 filed? No If not, is well log attached? Yes Producing Formation(s): Herrington, Krider, Winfield

API Number: 15-093-00616-00-00 Lease Name: Dienst Well Number: #1 Spot Location (QQQQ): APP - NE - NE - SW - GEN - OF - SEC 2310 Feet from North / South Section Line 2310 2970\* Feet from East / West Section Line Sec. 14 Twp. 22 S. R. 36 East West County: Kearny Date Well Completed: May 29, 1954 Plugging Commenced: May 5, 1954 Plugging Completed: November 20, 2003

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Fresh Water and Chase Series.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from 2671' feet to G.L. feet each set.

Hook onto 5 1/2" casing and bullhead 25 sacks of 40-60 Poz H cement and 6% gel to set plug at 2588' with 500# of cottonseed hulls. Let set 30 minutes. Load 5 1/2" casing to check for casing leak. Pump 145 sacks of 60-40 Poz H down 5 1/2" casing to displace with fresh water. Hook onto backside surface and pump 50 sacks of 60-40 Poz H + 6% gel and 1/4# per sak flo-cele and loaded backside. Cut 8 5/8" & 5 1/2" off and weld cap to abandon.

Name of Plugging Contractor: Halliburton License #: 5287 99997 Address: Liberal, Kansas

Name of Party Responsible for Plugging Fees: Kansas Natural Gas Operating, Inc. State of Kansas County, Haskell, ss.

Steve M. Lehning @ Kansas Natural Gas (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Steven M. Lehning, Supt. Kans. Nat. Gas Oper. Inc. (Address) P.O. Box 815, Sublette, KS 67877

SUBSCRIBED and SWORN TO before me this 21st day of November, 2003

Kraig L. Gross, Notary Public My Commission Expires: 5-8-06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas

