

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

TYPE OR PRINT
NOTICE: Fill out Completely
and return to cons. div.
office within 30 days.

API NUMBER 15-051-25156 - 00-00
LEASE NAME Greenhouse
WELL NUMBER 1
1980 ft. from S Section Line
1320 ft. from E Section Line
SEC. 31 TWP. 13 RGE. 17 (E) or (W)
COUNTY Ellis

Date Well Completed * 10/03/2002
Plugging Commenced * 11/19/03 - 11/20/2003
Plugging Completed * 11/20/03 11/20/2003
* Per CP 2/3 (date)

LEASE OPERATOR Ottley Oil Co.
ADDEESS 810 Vine, Hays, KS 67601
PHONE # (785) 625-7800 OPERATORS LICENSE NO. 33234
Character of well oil
(Oil, Gas, D&A, SWD, input, Water Supply Well)
The plugging proposal was approved on 11/19/03
by Herb Deines (XCC District Agent's Name)

RECEIVED
NOV 25 2003
KCC WICHITA

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3606
Show depth and thickness of all water, oil and gas formations
OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	219-220*	none
				5 1/2	3604	2440

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set

Sand at 3309, bail 5 sx cem. Rip pipe at 2440, pull to 1900, pump 100 sx cem. and 3 sx hulls. Pull to 1250, pump 30 sx cem. and 1 sx hulls. Pull to 650, pump 30 sx cem. and 1 hulls. Pull to 200, circulate to surface w/25 sx. Pull rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Quality Well Service, Inc.

STATE OF Rice COUNTY OF Kansas, ss.

Richard McIntyre (Employee of Operator) or (Operator) of
above - described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above - described well as filled that
the same are true and correct, so help me God.

(Signature) Richard O. McIntyre
(Address) 401 West Main, Lyons, KS 67554

SUBSCRIBED AND SWORN TO before me 24th day of November, 2003

Margaret Melcher
Notary Public

My commission Expires: 2-15-07

