

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21072-00-00
Spot: SEWNWE Sec/Twnshp/Rge: 18-13S-21W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: WERTH A Well Number: 1
County: TREGO Total Vertical Depth: 4150 feet

Operator License No.: 33069
Op Name: ENCORE OPERATING COMPANY
Address: 1601 BLAKE STREET, SUITE 500
DENVER, CO 80202

Production Casing Size: 5.5 feet: 4147 w/175 sxs cmt
Surface Casing Size: 8.625 feet: 247 w/175 sxs cmt

\$134.88

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/24/2003 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: ROLAND NYP Company: ENCORE OPERATING COMPANY Phone: (303) 595-9251

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
DV at 1647'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/24/2003 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 2050'.
Mixed and circulated cement with 190 sxs cement and 500# hulls.
POOH. Swaged onto 5 1/2" - pumped 90 sxs cement.
Max. P.S.I. 400#. S.I.P. 200#.
Hooked up to the annulus and pumped 10 sxs cement.

RECEIVED
DEC 03 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED
DATE 12-8-03
INV. NO. 204060858

Form CP-2/3

DEC 01 2003

TRIPLE "H" OIL OPERATIONS

REPLACEMENT CARD

P.O. BOX 248
HAYS, KS 67601

#1 WERTH

18-13-21W
SE NW NE

CONTR DREILING OIL, INC.

CTY TREGO

GEOLOGICAL

FIELD WC (RIGA NW DISC)



ELV 2213 KB SPD 8/13/82 CARD ISSUED 2/17/83

IP OIL WELL

API 15-195-21,072

MARM - INTV NA

LOG	Tops	Depth/Datum
ANH		1644 + 569
B/ ANH		1685 + 528
TOP		3294-1081
HEEB		3521-1308
TOR		3540-1327
LANS		3555-1342
BKC		3797-1584
MARM		3888-1675
ARB		3972-1759
RTD		4150-1937

8 5/8 " 247; 5 1/2 " 4147

DST (1) 3710-91 (LANS) / 30-30-0-0, REC 10, QCM, ISIP 355#
IFP 41-50#, BHT 120°

DST (2) 3882-3918 (PENN) / 30-30-45-30, REC 175, OIL (GR 35.5%), 300' G & MCO, SIP 1242-1226#, FP 58-132 / 132-223#
BHT 124°

DST (3) 3955-75 (MARM, ARB) / 30-30-0-0, REC 15, SOGM, ISIP 25#; IFP 8-17#; BHT 122°

MICT - CO. PF (MARM) INTV NA, SWB DWN SO POP, NO OTHER INFO TO BE RELEASED AT PRESENT. WILL RELEASE INFO WHEN AVAILABLE - TEMP COMP - 7/21/83

INFO RELEASED: 7/21/83 - WAS OIL WELL - TIGHT HOLE

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

1WAD10555