

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23238-00-00  
Spot: SWNE . . . .Sec/Twnshp/Rge: 7-13S-13W  
4290 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: HOLLAND Well Number: 1-7  
County: RUSSELL Total Vertical Depth: 3365 feet

Operator License No.: 5146  
Op Name: RAINS & WILLIAMSON OIL CO., INC.  
Address: 220 WEST DOUGLAS, STE 200  
WICHITA, KS 67202

Surface Casing Size: 8.625 feet: 460

#10936

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/20/2003 12:00 PM

Plug Co. License No.: 9431 Plug Co. Name: VONFELDT DRILLING, INC

Proposal Rcvd. from: DOUG BUDIG Company: VONFELDT DRILLING, INC Phone: (785) 483-6446

Proposed Plugging Method: Order 145 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 11/20/2003 3:30 PM

KCC Agent: HERB DEINES

**Actual Plugging Report:**

1st. Plug at 3319' w/25 sxs. Arbuckle top at 3329'.  
2nd. Plug at 850' w/25 sxs. Anhydrite 820' - 852'.  
3rd. Plug at 525' w/60 sxs. Surface pipe to 460'.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

RECEIVED  
DEC 05 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED

DATE 12-8-03

INV. NO. 2004060868

Form CP-2/3

DEC 03 2003