

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-29020-00-00
Spot: SWSWSWNE Sec/Twnshp/Rge: 27-26S-18E
2800 feet from S Section Line, 2600 feet from E Section Line
Lease/Unit Name: CASPER/SOLOMON Well Number: 8
County: ALLEN Total Vertical Depth: 845 feet

Operator License No.: 5488
Op Name: TWM PRODUCTION CO.
Address: 1150 HWY 39
CHANUTE, KS 66720

Surface Casing Size: 7 feet: 21

#35⁰⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/01/2003 1:00 PM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY
Proposal Rcvd. from: MIKE WIMSETT Company: TWM PRODUCTION CO. Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED BORE TO 845'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT TD, A 50' CEMENT PLUG AT 500', AND A CONTINUOUS CEMENT PLUG FROM 200' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 12/01/2003 2:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

PIPE WAS RAN INTO THE WELL TO 845'. THE WELL WAS GELLED FOR BRIDGING PURPOSES. 20 SACKS OF CEMENT WERE PUMPED THROUGH THE PIPE TO 845'. THE PIPE WAS PULLED TO 500' AND 20 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE PIPE WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 92 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
KCC District #3
DEC 08 2003
KCC WICHITA
DEC 4 2003
Chanute, KS

Remarks:

Plugged through:

District: 03

Signed Clayton Titel by [Signature]
(TECHNICIAN)

DATE 12-8-03
WV. NO. 2004060872