

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-01050-00-01
Spot: NESESW Sec/Twnshp/Rge: 11-25S-15W
990 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: WILSON OWWO Well Number: 1
County: STAFFORD Total Vertical Depth: 4500 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

Production Casing Size: 4.5 feet: 4290 WITH 110 SX CMT
Surface Casing Size: 10.75 feet: 966 WITH 966 SX CMT

#146²⁵

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/14/2003 2:15 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: SAND BACK TO 4144' WITH 4 SX CMT. PLUG AT 1000' WITH 70 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: _____ WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/14/2003 3:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:


PERFS AT 4194-97, 4199-4201, 4205-10, 4213-16, 4218-21'. SANDED BACK TO 4101' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 1000' WITH 15 SX GEL & 70 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED
DEC 04 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2030' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE 12-8-03
INV. NO. 2004060862

Form CP 27