

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20952-00-00

Spot: W2SW

Sec/Twnshp/Rge: 11-28S-40W

1320 feet from S Section Line, 660 feet from W Section Line

Lease/Unit Name: LUCAS

Well Number: 1-1211

County: STANTON

Total Vertical Depth: 5650 feet

Operator License No.: 32855

Conductor Pipe Size: 13.375 feet: 527 WITH 375 SX CMT

Op Name: TE-RAY ENERGY, INC.

Production Casing Size: 4.5 feet: 5654 WITH 150 SX CMT

Address: 1105 SOUVEREIGN ROW, UNIT C
OKLAHOMA CITY, OK 73108

Surface Casing Size: 8.625 feet: 1685 WITH 650 SX CMT

\$18363

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 11/17/2003 2:00 PM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON

Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed
Plugging
Method:

PUMP 300# HULLS & 20 SX CMT. PLUG AT 1690' WITH 50 SX CMT. PLUG AT 600' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/18/2003 10:00 AM

KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 5614'. PERFS AT 5318-44'. PUMPED 300# HULLS WITH 20 SX CMT. DISPLACE WITH MUD & PRESSURE TO 500# AND SHUT IN. 1ST PLUG PULL OUT OF HOLE TO 1700'. CIRCULATE HOLE MUD & PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 600'. LOAD HOLE & PUMP 30 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. SDON. 11/18/2003: LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED
DEC 09 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2824' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED

DATE 12-9-03

WEL. NO. 2004060885

Form CP-24