

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-187-20235-00-00  
Spot: S2 Sec/Twnshp/Rge: 9-28S-40W  
1320 feet from S Section Line, 2640 feet from E Section Line  
Lease/Unit Name: FLOYD Well Number: 2-9  
County: STANTON Total Vertical Depth: 2830 feet

Operator License No.: 4824  
Op Name: PIONEER NATURAL RESOURCES USA.  
Address: 5205 N. O'CONNOR BLVD.  
IRVING, TX 75039

Production Casing Size: 5.5 feet: 2829 WITH 600 SX CMT  
Surface Casing Size: 8.625 feet: 649 WITH 350 SX CMT  
*#9198*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/18/2003 3:30 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DAVID HIGGINS Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 500# HULLS & 25 SX CMT. SPACER TO 650'. FILL 5 1/2" WITH CMT FROM 650' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND  
Date/Time Plugging Completed: 11/18/2003 5:00 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 2828'. PERFS AT 2497-2560'. PUMP 500# HULLS WITH 25 SX CMT. FOLLOW BOTTOM PLUG WITH 42 BBL MUD. CHECK WITH FLOAT @ 650'. PUMP 90 SX CMT TO FILL 5 1/2" FROM 650' TO SURFACE. PUMP 10 SX CMT DOWN BACKSIDE. PRESSURE UP & SHUT IN.

RECEIVED  
DEC 09 2003  
KCC WICHITA

Remarks: USED COMMON CMT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

*Jim Holland*  
(TECHNICIAN)

INVOICED  
DATE 12-9-03  
# 2004060884

*[Signature]*