

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20365-00-00  
Spot: NWSE Sec/Twnshp/Rge: 18-28S-34W  
1980 feet from S Section Line, 1980 feet from E Section Line  
Lease/Unit Name: TATON G L Well Number: 1  
County: HASKELL Total Vertical Depth: 3092 feet

Operator License No.: 5952  
Op Name: BP AMERICA PRODUCTION COMPANY  
Address: 2225 WEST OKLAHOMA AVENUE  
ULYSSES, KS 67880

Production Casing Size: 5.5 feet: 3171 WITH 1300 SX CMT  
Surface Casing Size: 8.625 feet: 1723 WITH 950 SX CMT

*#10049*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/03/2003 1:30 PM  
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES  
Proposal Rcvd. from: SUE SELLERS Company: \_\_\_\_\_ Phone: (281) 366-2052

Proposed Plugging Method: PUMP 600# HULLS WITH 15 BBLs GEL WATER THEN 216 SX CMT DOWN 5 1/2" CASING. PRESSURE TEST. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 12/03/2003 3:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:


PERFS AT 2950-2970 & 2986-3020'. 1ST PLUG PUMP 600# HULLS WITH 15 BBL GEL WATER THEN 216 SX CMT DOWN 5 1/2" CASING. SHUT IN PRESSURE 500#. 2ND PLUG PUMPED 20 SX CMT DOWN 8 5/8" X 7" ANNULUS. SHUT IN PRESSURE 300#.

RECEIVED  
DEC 09 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed \_\_\_\_\_ (TECHNICIAN)

INVOICED  
DATE 12.9.03  
INV. NO. 2004060880

Form 5-1/3 *[Signature]*