

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15-065-21165 - 00 - 00

LEASE NAME ROME UNIT

WELL NUMBER #3-1

NOTICE: Fill out completely and return to Cons. Div. office within 30 days
880 Ft. from S Section Line
880 Ft. from E Section Line

LEASE OPERATOR Murfin Drilling Co., Inc.

SEC. 27 TWP. 9S RGE. 25W (E) or (W)

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202

COUNTY GRAHAM

PHONE # () 267-3241 OPERATORS LICENSE NO. 30606

Date Well Completed 9/17/79 12/18/1979

Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging commenced 11/7/03

Plugging Completed 11/7/03

The plugging proposal was approved on 11/7/03 9/22/03 (date)

by Rich Williams @ KCC in Hays, KS. (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation Lansing/Kansas City Depth to Top 3918 Bottom 4049 TD4315' Show

depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	221'	8 5/8	221	0
		production	4307'	4 1/2	4307	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Perf 4 1/2" csg @ 2200' & 1375'. Tied onto 4 1/2" csg. Pumped 160 sxs SMD & 500# hulls. Max press 500#. ISIP 100#. Tied onto 8 5/8". Pumped 50 sxs SMD, 100# hulls. Max press 100#. ISIP 50#. Loaded 4 1/2" csg w/10sxs SMD. Tied onto 8 5/8". Pumped 30 sxs SMD & SI. Witnessed & approved by Rich Williams w/KCC @ Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Tom Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature] (Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 12th day of November, 2003

Notary Public - Barbara J. Dodson [Signature] My Commission Expires: 12/16/03 Form CP-4

Revised 05-88

RECEIVED DEC 08 2003 KCC WICHITA



SWIFT SERVICES, INC.

PO BOX 466

NESS CITY, 67560-0466

Invoice

DATE	INVOICE #
11/7/03	5820

DEC 1 2003

BILL TO
Murfin Drilling Co Inc PO Box 130 Hill City, KS 67642

PA
APPROVED *[Signature]*

RECEIVED
DEC 08 2003
KCC WICHITA

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Operator	Job Purpose
Net 30	3-1 ✓	Rome ✓	Graham		Oil	Abandoned	Lenny	PTA

PRICE REFERENCE...	DESCRIPTION	QTY	UNIT PRICE	AMOUNT
575W	Milage	60	2.50	150.00T
576W-P	Pump Charge	1	550.00	550.00T
275	Cotton Seed Hulls	8	20.00	160.00T
330	Swift Multi-Density	250	9.75	2,437.50T
581W	Service Charge Cement	250	1.00	250.00T
583W	Drayage	745.5	0.85	633.68T
	Subtotal			4,181.18
	Sales Tax		5.30%	221.60

Thank you for your business.	Total	\$4,402.78
-------------------------------------	--------------	-------------------



CHARGE TO: Murphy Dalg Co.
 ADDRESS: _____
 CITY, STATE, ZIP CODE: Hill City, Ks

RECEIVED
 DEC 08 2003
 MCC WICHITA

TICKET No 5820

PAGE 1 OF 1

SERVICE LOCATIONS: 1. Hays Ks
 WELL/PROJECT NO. 3-1 LEASE Rome COUNTY/PARISH Graham STATE KS CITY _____ DATE 11-7-03 OWNER Same
 2. TICKET TYPE SERVICE CONTRACTOR _____ RIG NAME/NO. _____ SHIPPED VIA 105 DELIVERED TO S.W. Hill City ORDER NO. _____
 3. WELL TYPE oil WELL CATEGORY Abandoned JOB PURPOSE P.T.A WELL PERMIT NO. _____ WELL LOCATION _____
 4. REFERRAL LOCATION _____ INVOICE INSTRUCTIONS _____

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
575					MILEAGE	105	60	mi		2.50	150.00
576					Pump charge		1	EA			550.00
275					Hulls		8	SKS		20.00	160.00
330					SMD Cement		250	SKS		9.75	2437.50
581					Bulk Service charge		250			1.00	250.00
583					Drayage		745	50	T.M.	.85	633.68

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X
 DATE SIGNED 11-7-03 TIME SIGNED 9:00 A.M. P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?				4181.18
WE UNDERSTOOD AND MET YOUR NEEDS?				
OUR SERVICE WAS PERFORMED WITHOUT DELAY?				TAX 221.60
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL 4402.78
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND				

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR [Signature] APPROVAL [Signature]

Thank You!

JOB LOG

SWIFT Services, Inc.

DATE 11-7-03 PAGE NO. 1

CUSTOMER MURFIN DRUG CO.

WELL NO. 3-1

LEASE Rome

JOB TYPE P.T.A

TICKET NO. 5820

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	0900							on loc Hookup to 4 1/2 CSC Bottom Perf 4049' shot Perfs at 2200 + 1375 8 5/8 at 221'
140			78 BBL				500	Down 4 1/2 Pump 140 SKS SMD cmt + 500 #hulls max PSI 500 shut in 4 1/2 w/ 100 PSI
50			28 BBL				100	hook up to 8 5/8 + Pump 50 SKS SMD cmt max PSI 100 shut in w/ 50 PSI
20			11 BBL				400	hook backup to 4 1/2 well on vac took 4 BBL to load Pump 20 SKS cmt PSI to 400 shut in
	1010							wait 1HR + Topoff IF needed Topoff 4 1/2 w 10 SKS
10 30								Pump 30 SKS Down 8 5/8
	1100							Job Complete
								4 1/2 170 SKS cmt 500 hulls
								8 5/8 80 SKS cmt

RECEIVED

DEC 08 2003

KCC WICHITA