

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-195-21506-00-00

RECEIVED

NOV 25 2003

KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Com. Div.  
office within 30 days.

LEASE NAME Shaw Creek Unit

WELL NUMBER BR 12

2970 Ftt. from Per Original Section Line

4950 Ftt. from E Section Line

SEC. 28 TWP. 11 RGE. 22 XXX or (Y)

COUNTY Trego

Date Well Completed 6/7/1984

Plugging Commenced 10-6-03

Plugging Completed 10-6-03

LEASE OPERATOR Charter Energy, Inc.

ADDRESS PO Box 252, Great Bend, KS 67530

PHONE (620) 793-9090 OPERATORS LICENSE NO. 9090

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-6-03

by KCC District #4 - Mr. Herb Deines (date)  
(KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached?

Marmaton - Toronto  
Producing Formation LKC Depth to Top 3607 Bottom 3966 T.D. PBTD 4020

Show depth and thickness of all water, oil and gas formations.

4054  
Per CP 2/3

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size   | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 288    | 0          |
|           |         |      |    | 4 1/2" | 4038   | 0          |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
Tubing and packer lost in hole. Top of tubing @ 1663. Ran tubing to 1600'.  
Spot 35 sx 60 - 40 POS - 10% Gel. Pull to 700'. Spot 55 sx w/400# hulls.  
Pull tubing & top off casing. Pressure to 500#. Tie out 4 1/2 - 8 5/8 annulus.  
Pump 10 sx & pressure to 500#.

Name of Plugging Contractor Professional Pulling Services, LLC  
Allied Cementing Co., Inc. License No. ? 32810

Address P O Box 31, Russell, KS 67665

Per CP 2/3

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Charter Energy, Inc.

STATE OF Kansas COUNTY OF Barton, s.s.

Charter Energy, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above described well as filed the same are true and correct, so help me God.

(Signature) Steve Baize  
Steve Baize  
(Address) PO Box 252, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 19th day of October, 2003.

Donna Moore  
Donna Moore Notary Public

My Commission Expires: 2/17/05

