

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION RECEIVED  
 OIL & GAS CONSERVATION DIVISION  
 WELL PLUGGING RECORD DEC 01 2003  
 K.A.R. 82-3-117

Form CP-4  
 September 2003  
 Type or Print on this Form  
 Form must be Signed  
 All blanks must be Filled

KCC WICHITA

Lease Operator: Kaiser-Francis Oil Company

Address: PO Box 21468 - Tulsa OK 74121-1468

Phone: (918) 491-4314 Operator License #: 6568

Type of Well: Oil Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 10/02/03 (Date)

by: Steve Durant (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)  
Marmaton Depth to Top: 5168' Bottom: 5172' T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. 6540'

API Number: 15-119-10239-00-01

Lease Name: Adams Ranch

Well Number: 1-12

Spot Location (QQQQ): \_\_\_\_\_ - SW - NE - NW

990 Feet from  North /  South Section Line

1650 Feet from  East /  West Section Line

Sec. 12 Twp. 35 S. R. 30  East  West

County: Meade

Date Well Completed: re- 3/13/02

Plugging Commenced: 10/02/03

Plugging Completed: 10/03/03

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Marmaton	Oil	5168	5172	9" <sup>6.25" <sub>cl 2/3</sub></sup>	1401'	0
				5 1/2"	6314'	2500'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Set plugs as follows: Pump 25 sks of cmt., 100# hulls from 5000' - 5172'. 60 sks of cmt. from 1430' - 1230'

45 sks of cmt. from 690' - 570', 15 sks of cmt. from 40' - 0'. With mud spacing each plug.

Name of Plugging Contractor: Sargent & Lillard Casing Pulling Inc. License #: 32833

Address: PO Box 1450 - Woodward OK 73802-1450

Name of Party Responsible for Plugging Fees: Kaiser-Francis Oil Company

State of Oklahoma County, Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED and SWORN TO before me this 26th day of November, 20 03

Wynona Yates  
 Notary Public

My Commission Expires: \_\_\_\_\_



Mail to: KCC - Conservation Division, 130 S. Market - Room 207