

STATE OF KANSAS
OIL AND GAS COMMISSION
S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-009-64709-00-00
API NUMBER _____ Comp. 1951

LEASE NAME Lanterman

WELL NUMBER 11

4450 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 23 TWP. 19 RGE. 12W (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 11-19-03

Plugging Completed 11-19-03

DEC 04 2003 NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

OPERATOR RUSSELL OIL INCORPORATED

ADDRESS P.O. Box 1469 Plainville, IL. 60544

PHONE (815) 609-7000 OPERATORS LICENSE NO. 3293

Character of Well Oil

(i.e., Gas, D&A, SWD, Input, Water Supply Well)

Plugging proposal was approved on 4-29-03 (date)

Case Morris (KCC District Agent's Name).

ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3426' 3421'

Per CP 2/3

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf.</u>				<u>8-5/8"</u>	<u>265'</u>	<u>None</u>
<u>Prod.</u>				<u>5-1/2"</u>	<u>3418'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each shot. Shot 5-1/2" casing @ 1475' and 700'. Ran 2" tubing to 1480', hooked onto backside and pumped 25 sacks 60/40 10% gel, press. up to 700#, shut-in 400#. Tied onto tubing and circulated 145 sacks w/550# hulls. Pulled tubing and pumped 120 sacks and 250# hulls down 5-1/2" casing. Pressured up to 700#, shut-in 400#. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Russell Oil, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 3rd. day of December, 20 03

My Commission Expires: _____



Notary Public