

RECEIVED  
DEC 10 2003  
KCC WICHITA

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-101-20431-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 4/04

WELL OPERATOR Abercrombie Energy, LLC KCC LICENSE # 32457  
(owner/company name) (operator's)

ADDRESS Rt. #1, Box 56 CITY Great Bend

STATE Kansas ZIP CODE 67530 CONTACT PHONE # ( ) 620-793-8186

LEASE Anderson 'B' WELL# 1 SEC. 33 T. 16 R. 27 (East/West)

N/2 - NE - NE SPOT LOCATION/QQQQ COUNTY Lane

660 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM (E/W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 290 CEMENTED WITH 190 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 4391 CEMENTED WITH 250 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4220-23' 4263-65'

ELEVATION 2709/2714 T.D. 4220 PBDT 4361 ANHYDRITE DEPTH 2133-2169'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING In compliance with rules & regulations  
with state of Kansas.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?  IS ACO-1 FILED?

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

E. L. Abercrombie PHONE# ( ) 620-793-8186

ADDRESS Rt. #1, Box 56 City/State Great Bend, Kansas 67530

PLUGGING CONTRACTOR Mike's Testing & Salvage, Inc. KCC LICENSE # 31529

ADDRESS P. O. Box 467, Chase, Ks. 67524 PHONE # ( ) 620-938-2943  
(company name) (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Soon as possible.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 12-8-2003 AUTHORIZED OPERATOR/AGENT: E L Abercrombie  
(signature)

# Downhole Configuration Diagram

Operator: A.L. Abercrombie, Inc.  
 Well Name: #1 Anderson "B"  
 Spot Location: N/2 NE NE  
 S-T-R: Section 33-16S-27W  
 County: Lane County, Kansas  
 API: 15-101-20,431

RECEIVED  
 DEC 10 2003  
 KCC WICHITA

Spud Date: 1-29-80  
 Completion Date: 2-10-80  
 Date of First Production: 3-20-80  
 Purchaser: Koch  
 RTD: 4620' LTD: 4622' PBDT: 4361'  
 Wellsite Geologist: Ralph White

## Log Tops:

Anh 2133 (+581)  
 B/Anh 2169 (+545)  
 Tpk 3712 (-998)  
 Hb 3956 (-1242)  
 Tor 3975 (-1261)  
 Lans 3993 (-1279)  
 Stark 4246 (-1532)  
 BKC 4316 (-1602)  
 Marm 4355 (-1641)  
 Paw 4406 (-1692)  
 Ft Sc 4502 (-1788)  
 Cher 4526 (-1812)  
 Miss 4592 (-1878)  
 RTD 4620  
 LTD 4622

Elevation:  
2714' KB  
2709' GL

8 5/8" 20# surface casing  
 set at 290' w/ 190 sx.

## Drill Stem Test Information:

DST #1: (4076-4085) LKC "E" & "F"; 660' SW 1101-1101#  
 DST #2: (4144-4170) LKC "G" & "H"; 50' WM, 270' W  
 355-355#  
 DST #3: (4205-4224) LKC "J"; 1120' GIP, 278' CGO, 113' OGCM,  
 15' WM 857-846#  
 DST #4: (4270-4296) LKC "L"; 15' M w/so 1048-772#  
 DST #5: (4373-4410) Marm; 63' M w/so 53-43#

2 3/8" tubing set at 4361'

Top of Cement NA'

## Brief Well History:

2-29-80 Pf 4263-4265 (LKC "K") w/4 spf. Swb dry. Δc  
 4263-4265 (LKC "K") w/500 gal 15% Non-E.  
 Swb 12.08 BPH, 33% water. Set CIBP at 4250'.  
 3-4-80 Pf 4220-4223 (LKC "J") w/4 spf. Swb .90 BPH,  
 25% water. Δc 4220-4223 (LKC "J")  
 w/500 gal 15% Non-E. Swb 12.06 BPH, 14%  
 water.  
 3-6-80 Drilled out CIBP at 4250'; drove plug to 4337'.  
 Swb 12.07 BPH, 15% water (both zones  
 together.)  
 3-27-80 Water Analysis: Chlorides 61.400 mg/l; PH  
 6.6; Specific Gravity 1.086; recommend  
 treating this well with Corrosion Inhibitor #1.  
 4-30-80 Install cathodic protection: 23 volts, 15.5 amps.  
 5-7-80 State Production Test: 85 BOPD; 50% water.

▣ Pf 4220-4223 (LKC "J") w/4 spf

▣ Pf 4263-4265 (LKC "K") w/4 spf

## Producing Zones:

LKC "J" (4220-4223)  
LKC "K" (4263-4265)

## Zones Prior to Abandonment:

None

4 1/2" 10.5# production casing  
 set at 4391' w/ 250 sx.

RTD: 4620'

LTD: 4622'

PBDT: 4361'

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    John Wine, Commissioner    Robert E. Krehbiel, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Abercrombie Energy, LLC  
150 N. Main, STE 801  
Wichita, KS 67202

December 11, 2003

Re: ANDERSON B #1  
API 15-101-20431-00-00  
N2NENE 33-16S-27W, 660 FNL 660 FEL  
LANE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888

Sincerely  


David P. Williams  
Production Supervisor