

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24775-00-00
Spot: N2SWSE Sec/Twnshp/Rge: 8-16S-11W
990 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: WIRTH Well Number: 5
County: BARTON Total Vertical Depth: 3347 feet

Operator License No.: 6622
Op Name: SCHOENBERGER, J.L. D/B/A JASON OIL
Address: PO BOX 701 363 W 12TH ST
RUSSELL, KS 67665

Surface Casing Size: 8.625 feet: 369

108 78

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/05/2003 12:00 PM
Plug Co. License No.: 9431 Plug Co. Name: VONFELDT DRILLING, INC
Proposal Revd. from: WES PAFF Company: VONFELDT DRILLING, INC Phone: (785) 735-4142

Proposed Plugging Method: Ordered out 160 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.
No arbuckle cut.

Plugging Proposal Received By: RICHARD WILLIAMS
Date/Time Plugging Completed: 12/05/2003 10:00 PM

WitnessType: Plugging Operations Were Not Witnessed
KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 732' w/25 sxs.
2nd. Plug at 477' w/100 sxs.
3rd. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

RECEIVED
DEC 15 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED
DATE 12-15-03
INV. NO. 2004060953

Form CP-2/3

DEC 10 2003